



SDMS DocII

2198356

APPENDIX K

[F*·.



many former manufacturing operations, the practice of on-site disposal of both process and non-process residuals, and inherent uncertainties regarding timing, volumes, locations and substances, make it difficult to assess property-specific characteristics. Consequently, the study approach considers the FMC property by geographic study areas.

The following areas represent a reasonable spatial subdivision of the FMC property as a means of evaluating site characteristics and possibly identifying specific areas of concern:

- A. Former Surge Pond Area
- B. Former Coal Pile Area
- C. Former R & D Area
- D. Former Fermentation Area
- E. Former Sluiceway Area
- F. Inactive Disposal Area
- G. Southwest Plant Complex
- H. Stormwater Retention Basin Area
- I. Firewater Pond Area

These areas are identified on Figure 3. Note that many of the areas are the result of former practices. The remainder of this Report will address the overall FMC property by considering each property-specific study area.

2.03.3.1 Former Surge Pond Area:

The former surge pond area is the most hydraulically upgradient location on the FMC property. This area is contiguous to the existing Pounce manufacturing facilities. Chemical manufacturing has occurred in the former surge pond area since



before 1957. The surge pond itself was formerly used to collect stormwater runoff in the area. Water collected in the pond was pumped to treatment prior to permitted discharge to Stonehouse Cove. The surge pond was closed in 1983 and has since been removed.

2.03.3.2 Former Coal Pile Area:

The former coal pile area was reportedly used for coal storage for many years. Coal usage was discontinued in the early 1950's.

2.03.3.3 Former R & D Area:

The former R & D (research & development) area was previously used for various R & D applications. The buildings were demolished in 1972. Waste solvents were generated by the R & D facilities. A nearby subsurface steel tank was used to store spent solvents and reportedly was pumped out for disposal. The tank was subsequently excavated and removed.

2.03.3.4 Former Fermentation Area:

The former fermentation area previously contained buildings involved in the fermentation of molasses to various intermediate and end products. All of these buildings have been demolished. The basement of one of these buildings was reportedly used for open burning of trash and waste materials from offices and manufacturing. This building's foundation has since been filled with debris and rubble.



2.03.3.5 Former Sluiceway Area:

A concrete sluiceway was previously used to convey wastewater to the southern part of the plant site with ultimate discharge to Curtis Bay. The sluiceway was abandoned and backfilled in 1972.

2.03.3.6 Inactive Disposal Area:

The inactive disposal area had been used for many years for disposal of manufacturing wastes and construction debris. On-site disposal in this area ceased during 1975. Both its boundaries and contents are poorly defined. Available information indicates that a variety of bulk and containerized residues from chemical production were disposed in this area. Materials believed present include acetoacetarylides, carbamates, pyrethrum flower residues, 7-OH tar, 7-Nitro centrifuge bottoms, Ethion wastes, and Butacide tars.

2.03.3.7 Southwest Plant Complex:

The southwest plant complex, along the eastern shore of Stonehouse Cove, was the site of lagoons, water intakes and outfalls, and old process facilities. Between 1970 and 1980 the lagoons were filled, the outfalls decommissioned, and the shoreline recontoured. In addition, this area includes many gravity sewers, sumps and storage tanks associated with past and present manufacturing operations. The gravity sewers and sumps in this area are being inspected as part of a plant-wide program. Those facilities of questionable integrity have been and are being rehabilitated or removed. For example, a sump located near Well 8 was

inspected and was determined to have a sizable opening. The sump contained activated carbon and wastewater associated with the Calgon treatment system. The sump was cleaned and taken out of service until properly repaired.

2.03.3.8 Stormwater Retention Basin Area:

An impoundment was constructed around 1960 in the vicinity of the present Stormwater Retention Basin (SRB). This impoundment reportedly contained spent acid from the manufacture of Tedion, an agricultural chemical. This acid impoundment was removed from service in the early 1970s. It reportedly was excavated and residues were disposed off-site during expansion of the 7-OH Plant 3 facility.

The Stormwater Retention Basin was constructed in 1976 to collect stormwater runoff from the 7-OH plant area. It is presently a single clay liner surface impoundment, but is proposed to be removed and replaced with a dual cell, subsurface, rectangular concrete tank. Regulatory review, allocation of funds, engineering design, contractor selection, and equipment delivery will dictate the replacement schedule.

2.03.3.9 Firewater Pond Area:

The Firewater Pond was constructed in 1976, in conjunction with the Stormwater Retention Basin. The Firewater Pond contains brackish water pumped from Curtis Bay. It is used as a source of water to be used in the event of a fire.



APPENDIX L



DEPARTMENT OF THE ENVIRONMENT

201 WEST PRESTON STREET • BALTIMORE, MARYLAND 21201 AREA CODE 301 • 225-5647

William Donald Schaefer Governor Martin W. Walsh, Jr. Secretary

CONTROLLED HAZARDOUS SUBSTANCES FACILITY PERMIT

Permit Number:

A-023

Effective Date:

October 5, 1987

Expiration Date:

October 4, 1990

Pursuant to the Provisions of Health-Environmental Article, Section 7-232, Annotated Code of Maryland and regulations promulgated thereunder, the Office of Environmental Programs, Waste Management Administration, hereinafter referred to as "WMA" hereby authorizes

FMC Corporation Agricultural Chemical Group

to operate a controlled hazardous substances Incinerator facility located at 1701 East Patapsco Avenue, Baltimore, Maryland in accordance with the following special and general conditions including the attached map made a part hereof, and the provisions of COMAR 10.51. Applicable regulations are those which are in effect on the date of issuance of this permit.

This permit is based on the assumption that the information submitted in the permit application attached to the Permittee's letter dated August, 1981 as modified by subsequent amendments dated January 13, 1984; August 10, 1984; February 28, 1985; April 10, 1985; September 4, 1985; October 31, 1985; September 4, 1986; September 30, 1986; December 4, 1986; December 31, 1986; April 1, 1987; April 2, 1987; April 24, 1987; May 5, 1987; June 16, 1987; June 23, 1987; July 14, 1987; and July 29, 1987 (hereafter referred to as the application) is accurate and that the facility will be constructed and/or operated as specified in the pplication. Any inaccuracies found in this information may be grounds for the termination or modification of this permit (see COMAR 10.51.07.02 J) and potential enforcement action. The Permittee must inform the Will of any deviation from or changes in the information in the application which would affect the Permittee's ability to comply with the applicable regulations or permit conditions.



PART III - INCINERATION

A. WASTE IDENTIFICATION

- 1. The Permittee may not incinerate any off-site generated waste.
- 2. The Permittee shall incinerate only the following onsite generated wastes:

NON-CHS WASTES

Liquid Waste Streams

- a. Super Tar
- b. Claisen Tar
- c. 7-OH Tars (Plants I, III, IV)
- d. DV Ester Step 1 Waste
- e. DV Ester Step 3 Waste
- f. Plant 4 CD-101 Flush Oil
- g. Plant 4 Tars (U-11 and U-12 tars)
- h. Waste No. 2 Fuel Oil
- i. Waste Oil
- j. Command Herbicide Organic Waste Stream
- k. Diallyl Phthalates

Gaseous Waste Streams

- 1. Xylene Waste Gas Stream
- m. 7-OH Plant III Step I Gas Steam

CHS WASTES

- n. Second Basin Oil
- o. Third Basin Oil
- p. Waste Methanol
- q. TMOA Waste (trimethyl-orthoacetate)
- r. MAC Waste (Methallyl chloride)
- s. Allyl Alcohol/Ether

- t. Pounce Organics
- u. DV Ester Step 3 Head Cut C/A
- v. DV Ester Step 3 Bottoms
- w. Heptane
- x. Hexane
- y. Xylene from 7-OH
- z. Plant 4 Organics

B. WASTE FEED LIMITATIONS

- The Permittee shall incinerate wastes listed in (A) above within the specifications listed below, except as provided in B.2 below:
 - a. Total BTU loading from all wastes fed to the incinerator: less than or equal to 4.5×10^7 BTU/hour.
 - b. Total chlorine loading from all wastes fed to the incinerator: less than or equal to r.
 - c. Total ash loading: less than or equal to lbs/hour.
 - d. Viscosity of waste streams fed through the organics nozzle: less than or equal to 50 centipoise at 100°F.
 - e. Gaseous xylene waste feed rate: less than or equal to be ubic feet per minute (ACFM).

The Permittee, when incinerating CHS wastes listed in (A) above which contain Appendix V constituents shall comply with the specifications listed below:

- Waste methanol feed rate: less than or equal to 5%
- b. Combined feed rate of all 7-OH Tars: less than or equal to bs/hr.
- c. Waste Super Tar/Claisen Tar feed rate: less than
- d. Total ash loading: less than or equal to hour.

popular flow rate problem now problem now the flower

C. OPERATING CONDITIONS

- 1. The Permittee shall incinerate wastes listed in (A) only when the incinerator is operating within the specifications listed below:
 - a. Stack gas carbon monoxide (CO) concentration; less than or equal to:
 - i. 500 ppm average corrected to 7% oxygen for any ten minute period
 - ii. 100 ppm average corrected to 7% oxygen for any 60 minute period
 - b. In determining compliance with (a) above assume a constant 15% oxygen level in the stack gas.
 - c. Combustion chamber temperature as measured by the the combustion chamber: minimum of the combustion chamber: minimum when burning that the combustion chamber: minimum of the containts; minimum chamber that the containts of the containts of the containt appendix V constituents. Any excursions below these limits shall be for less than consecutive
 - d. Primary combustion chamber air flow, including the xylene waste gas stream: less than or equal to the combustion. Any excursions above this limit shall be for less than
 - e. Secondary combustion chamber air flow: less than or equal to the seconds. Any excursions above this limit shall be for less than sixty consecutive seconds.
 - f. Venturi quench column process water flow rate: greater than or equal to the Any excursions below this limit shall be for less than sixty consecutive seconds.
 - g. Venturi quench column make-up water flow rate: greater than or equal to Any excursions below this limit shall be for less than sixty (60) consecutive seconds.
 - h. Packed tower scrubber liquid flow rate: greater than or equal to the for less than city (60) consecutive seconds.

- j. Wet electrostatic precipitator (WESP) recirculating pump flow rate: greater than or equal to 160 gpm. Any excursions below this limit shall be for less than six consecutive seconds.
- k. WESP make-up water flow rate: greater than or equal to 18 gpm. Any excursions below this limit shall be for less than sixty (69) consecutive
- WESP DC voltage: greater than or equal to
 Any excursions below this limit shall be
 for less than sixty
- m. Combustion chamber pressure: less than atmospheric. Any excursions above atmospheric pressure shall be for less than compared (1) compared (2).
- 2. The Permittee may not introduce wastes into the incinerator unless the incinerator and associated equipment are operating within the conditions specified above.
- Within 120 days of permit issuance, the Permittee shall install, operate, maintain, and calibrate a system to off waste feed to the incinerator. This system shall be operated whenever CHS wastes containing Appendix V constituents are fed to the incinerator and shall be operated to shut off any CHS waste stream containing Appendix V constituents when the conditions listed below are violated.
 - a. Exhaust gas carbon monoxide concentration is greater than:
 - i. An average of 500 ppm for any ten-minute period corrected to 7% oxygen.
 - ii. An average of 100 ppm for any sixty-minute period corrected to 7% oxygen.
 - b. In determining compliance with a. above assume a constant 15% oxygen level in the stack gas.



- c. The incinerator combustion chamber temperature, as measured by the thermocouples in the combustion chamber, falls below for sixty (60) consecutive seconds.
- d. Primary combustion air flow including the gaseous xylene waste stream: grant and ACFM for sixty (20) consecutive seconds.
- e. The secondary combustion air flow: greater than for sixty (60) constitive seconds.
- f. Scrubber liquid flow rate: less than the forse per minute for sixty consecutive seconds.
- g. WESP DC voltage: less than 20 consecutive seconds.
- 4. If there is an incinerator shut-down or any of the automatic waste feed cut-off systems activate, the Permittee may not re-introduce waste to the incinerator until the cause of the incinerator shut down has been determined and the problem rectified.
 - The Permittee may not feed CHS wastes containing Appendix V constituents into the incinerator if any portion of the automatic waste feed cut-off system is inoperative, unless alternative monitoring approved by the Department is performed and monitored for manual shut down.
- 6. The Permittee may not operate the alternative monitoring required in (5) above for a period greater than the it is approved by the Secretary.
- 7. The Permittee shall stop all waste feed when changes in the waste feed or operating conditions are not in accordance with this permit.

D. PERFORMANCE STANDARDS

The Permittee shall operate and maintain the incinerator, in accordance with conditions III B and III C above, to meet the following performance standards:

1. A destruction and removal efficiency (DRE) greater than or equal to 99.99% for all Appendix V constituents.

- 2. When burning CHS wastes containing Appendix V constituents: a hydrogen chloride (HCI) emissions rate less than or equal to 4.0 lbs/hr or 1% of the HCI in the stack gas prior to entering any pollution control
- 3. A particulate matter emissions less than or equal to 0.030 grains per dry standard cubic foot corrected to 12% carbon dioxide
- 4. No stack gas emissions which are visible to human observers other than water in an uncombined form.

E. MONITORING AND INSPECTIONS

equipment.

1. The Permittee shall maintain, operate, and calibrate monitoring equipment which continuously monitors and records the following:

Parameter		Frequency of Calibration	
a.	carbon monoxide concentration of incinerator exhaust gas corrected to 7% oxygen with assumed 15% oxygen level in the stack gas	daily	
b.	combustion zone temperature	quarterly	
c.	primary combustion air flow	monthly	
d.	secondary combustion air flow	monthly	
e.	scrubber liquid flow rate	monthly	
ę.	WESP DC voltage	monthly	

- 2. The Permittee shall monitor and record the following operating parameters at least every two (2) hours during incineration of wastes: process and make-up water flows to the venturi quench column, WESP recirculating pumps flow rate, WESP make-up water flow rate, and scrubber water pH.
- 3. The Permittee shall thoroughly visually inspect the incinerator and associated equipment (pumps, valves, conveyors, pipes, etc.) at least daily for leaks, spills, fugitive emissions, and signs of tampering.



4. The Permittee shall test the incinerator emergency waste feed cut-off system and associated alarms at least monthly to verify operability.

F. RECORDKEEPING

The Permittee must maintain a written operating log at the facility. For each calendar day on which hazardous waste is burned, the log must contain the information specified below:

- 1. Total quantity of each waste burned.
- 2. Description of all maintenance performed.
- 3. Results of all monitoring, testing, and inspections as required in Section E.

G. REPORTING

- 1. The Permittee shall report to the Secretary all occurances in which the parameters listed in Section C violate the limits and time periods specified. The report shall describe the parameter, date, start time, duration and (where appropriate) magnitude of the exceedance. It shall also describe the cause of the exceedance, corrective measures taken to prevent reoccurrence and whether automatic shut down occurred. If there are no exceedances during a given period, the Permittee shall submit a report to that effect.
- 2. The Permittee shall submit the above compliance reports on a quarterly basis no later than fifteen (15) days after the end of each calendar quarter.
- 3. The Permittee shall immediately verbally report to the Secretary any period in which a portion of the automatic cut-off system is inoperative and it is being monitored by an alternative method for manual shutdown. A written report shall be submitted with the above quarterly report.

H. WASTE ANALYSIS

Throughout operation of the incinerator, the permittee shall conduct sufficient waste analysis to verify that waste feed to the incinerator is within the physical and chemical limits specified in this permit, as specified in Attachment 1, waste analysis and at a minimum each time there is a change in the composition of the waste due to a process change.

I. COMPLIANCE SCHEDULE

1. Within 120 days of issuance of this permit, the Permittee shall install a weste feed shut off system to comply with conditions C.3a above.

J. TEST SCHEDULE

Within 90 days of issuance of this permit, the Permittee shall allow the Department conduct a test to determine the HCl removal efficiency of the air pollution control devices associated with the incinerator.

K. CLOSURE

At closure, the owner or operator shall remove all hazardous waste and hazardous waste residues (including but not limited to ash, scrubber waters, and scrubber sludges) from the incinerator site, in accordance with Attachment 6.

LIST OF ATTACHMENTS

Attachment No.		. <u>App</u>	Applicability	
1:	Waste Analysis Plan		Y	
2.	Inspection Schedule	refer to the same	<u> </u>	
3.	Training Outline		<u>Y</u>	
4.	Contingency Plan		<u> </u>	
5.	Incinerator and Control System Description		<u> </u>	
6.	Closure Plan		<u> </u>	
7.	Financial Assurance		<u> </u>	
			•	

Ronald Nelson, Director
Waste Management Administration

Date Signed 1987

APPENDIX M



IN THE MATTER OF:

FMC Corporation

DEPARTMENT
OF
THE ENVIRONMENT

SERVE ON:

A. Parker Dean
FCM Corporation
1701 E. Patapsco Avenue
Baltimore, Maryland 21226

Hazardous and Solid Waste
Management Administration
2500 Broening Highway
Baltimore, Maryland 21224

C-0-89-057

COMPLAINT

- (1) WHEREAS, the State of Maryland, Department of Environment, Hazardous and Solid Waste Management Administration pursuant to the powers, duties and responsibilities vested in the Secretary of the Environment by Environment Article, (formerly the Health-Environmental Article). Sections 1-301, 7-201 through 7-268, inclusive, Annotated Code of Maryland, and delegated to Hazardous and Solid Waste the Director. Management Administration, has reasonable grounds to believe that FMC Corporation has violated Maryland law, regulations and Controlled Hazardous Substance Facility Permit A023. issued November 16, 1981, under Health-Environmental Article, Section 7-207. regarding storage of Controlled Hazardous Substances (CHS).
- (2) WHEREAS, on September 9, 1988 and September 28, 1988 an inspection by representatives of the Hazardous and Solid Waste Management Administration revealed that containers of CHS were leaking and in poor condition while in storage on the 7-OH



container storage pad. Said condition constitutes a violation of COMAR 10.51.05.03B, 10.51.05.09B and CHS Facility Permit A023 General Condition A.

- inspection by a representative of the Hazardous and Solid Waste Management Administration revealed that containers of CHS, namely Toluene were in storage in an unpermitted CHS container storage area. Said condition constitutes a violation of COMAR 10.51.05.03B and CHS Facility Permit A023 General Condition A.
- (4) WHEREAS, on September 28, 1988 a review of the inspection log for the 7-0H container storage pad revealed that no notations were made on leaking and poor condition containers noted between September 9 and September 28, 1988. Said condition constitutes a violation of COMAR 10.51.05.02E4, 10.51.05.09E and CHS Facility Permit A023 General Condition A.
- representative of the Hazardous and Solid Waste Management Administration revealed that thirty-six (36) fifty-five gallon drums marked CHS were in storage outside the permitted CHS container storage area. Said condition constitutes a violation of COMAR 10.51.05.03B and CHS Facility Permit A023 General Condition A.

ORDER

OPIGINAL

THEREFORE, it is ORDERED by the Director of the Hazardous and Solid Waste Management Administration that FMC Corporation shall:

- 1. Inspect and maintain all Controlled Hazardous Substance containers as required by all applicable COMAR 10.51 regulations and FMC Controlled Hazardous Substance Facility Permit A023 General Condition A.
- 2. Maintain all inspection logs required for each Controlled Hazardous Substance unit as required by COMAR 10.51 and FMC Controlled Hazardous Substance Facility Permit A023 General Condition A.

CIVIL PENALTY

- (A) The Hazardous and Solid Waste Management Administration is seeking a civil penalty in this case of \$4,000.00.
- (B) FMC Corporation has a right to a hearing pursuant to Environment Article, Sections 7-261 (9-337), Annotated Code of Maryland. The Office of Hearings will issue a notice of hearing date and location unless prepayment of the civil penalty is made. Prepayment would constitute a waiver of a hearing.

ORIGINAL PROOF

- (C) An appearance before the Hearing Examiner constitutes an administrative hearing and FMC Corporation has the rights of any party in a contested case provided by the Maryland Administrative Procedure Act, State Government Article, Section 10-201, et seq., Annotated Code of Maryland.
- (D) Depending upon the evidence presented at the hearing, the Office of Hearings may assess any penalty up to \$1,000.00 for each day a violation existed or a maximum of \$50,000.00.

PROCEDURE FOR REQUESTING A HEARING ON THE COMPLAINT AND ORDER

(E) FMC Corporation may obtain a hearing to contest the Complaint portion of this document by filing a written request for a hearing within ten (10) calendar days of receipt of this document in accordance with the Maryland Administrative Procedure Act, State Government Article, Section 10-201, et seq., and in accordance with the Environment Article, Section 7-261, (9-337), Annotated Code of Maryland. Such a request should be sent to Chief Hearing Examiner, Office of Hearings, 3th Floor, 2500 Broening Highway, Building # 30, Baltimore, Maryland 21224, with a copy to the Attorney who signed this document, at the Office of the Attorney General, Department of the Environment, 2nd Floor, 2500 Broening Highway, Building # 30, Baltimore, Maryland 21224.



an administrative hearing, the attorney must be admitted to the Bar in the State of Maryland or must be specially admitted to the Maryland Bar pursuant to Maryland Rule 20 of the Maryland Rules governing admission to the Bar. Rule 20 governs special admission of out-of-state attorneys.

If you have any questions concerning this matter, please contact Mr. Joseph Stang, Inspector, Hazardous Waste Enforcement Division, Hazardous and Solid Waste Management Administration, at (301) 631-3400.

December 2,1988

Ronald Nelson, Director Hazardous and Solid Waste Management Administration

Approved as to form and legal sufficiency this 30 Mday of November, 1988.

Assistant Attorney General



APPENDIX N



CLOSURE CERTIFICATION

STORMWATER RETENTION BASIN

FMC CORPORATION BALTIMORE, MARYLAND

DECEMBER 1988

O'BRIEN & GERE ENGINEERS, INC. 1304 BUCKLEY ROAD SYRACUSE, NEW YORK 13221



TABLE OF CONTENTS

SECTION 1	- INTRODUCTION	PAGE			
	Background	1			
-	Objectives	2			
SECTION 2	- CLOSURE ACTIVITIES				
	Inventory Management	3			
2.02	Facility Decontamination	3			
2.03	Cover Installation	5			
2.04	Leachate Management	6			
2.05	Closure Certification	7			
FIGURES					
1	Site Plan				
2	Projected Closure Schedule	. 4.			
APPENDICES	3				
A.	Stabilized Residue/Fabrication Disposa	l Manifest Summary			
₿.	B. Soil Sample Figure/Test Results				
C.	Decontamination Wipe Test Results				
D.	Clay Source Test Data				
E.	E. Compacted Soil Backfill Test Results				
F. Compacted Clay Test Results					
G.	Cover Layer Test Results				

EXHIBITS

A. Closure Plan Approval



SECTION 1 - INTRODUCTION

1.01 Background

FMC Baltimore utilized a Stormwater Retention Basin to collect site runoff prior to on-site treatment and discharge to municipal sewer systems. Figure 1 is a site plan showing the location of the impoundment within the FMC property. The basin was constructed during 1976 and placed in operation in March 1977.

Analysis of basin influent and contents indicated that the impoundment occasionally contained liquids with a pH greater than 12.5 or less than 2.0. Therefore, the impoundment was classified as a hazardous waste storage facility and subject to the provisions of RCRA and COMAR 10.51. A RCRA Part B application was submitted to the State of Maryland in November 1985.

FMC decided to replace the impoundment with a tank system. Evaluation of several alternatives resulted in the selection of a below grade concrete tank with a primary and secondary HDPE liner. The selected location for the replacement facility was the same as the surface impoundment to take advantage of existing waste water and storm water transfer facilities.

A Closure Plan for the surface impoundment was submitted to the State of Maryland (State) and United States Environmental Protection Agency (EPA) in June 1987. A public hearing was held in September 17, 1987 to provide an opportunity for public comment on the Closure Plan. On October 6, 1987 the State approved the Closure Plan with the modifications presented in Exhibit A.



The construction of the replacement tank system was integral to the closure of the surface impoundment. Consequently the closure schedule, presented as Figure 2, resulted in completion of closure when the new facility was operational. The facility completed start-up testing during 1988.

1.02 Objectives

The approved Closure Plan included the submission of Closure Certification by both an independent Professional Engineer and FMC that the impoundment had been closed in accordance with the approved Closure Plan. The purpose of this Closure Certification Report is to document testing conducted during closure activities and provide a certification by an independent engineer that closure was completed in accordance with the approved Closure Plan.



SECTION 2 - CLOSURE ACTIVITIES

2.01 Inventory Management

when construction on the impoundment began it contained stormwater runoff and residual sludge. These substances were managed differently.

The storm water was pumped from the impoundment to the existing waste water treatment system for pre-treatment prior to discharge to the Patapsco waste water treatment facility. In addition, any water which entered the construction area during closure was managed in the same way.

The residual sludge was solidified using calcium oxide in roll off boxes. The solidified material was then transferred to transport vehicles for disposal at the permitted hazardous waste management facility operated by GSX Services (SCD070375985) located in Pinewood, South Carolina. Appendix A summarizes the information on shipments of solidified residue to the GSX disposal facility. The total mass of residue stabilized and disposed of off-site was approximately 1097 tons.

2.02 Facility Decontamination

Facility and equipment decontamination included several different operations. FabriForm erosion protection was removed and where contaminated disposed of in an off-site permitted facility. Equipment used during the operation of the impoundment was either stored and reused with the replacement tank, decontaminated, or disposed of off-site at a permitted facility.



Construction equipment was decontaminated on site, in accordance with the Closure Plan, prior to leaving the work area.

The stained FabriForm and other concrete removed from the impoundment was transported to the GSX facility in Pinewood, South Carolina. Appendix A presents a summary of shipments based on the copies of manifests retained by FMC. The total mass of FabriForm and concrete sent to GSX was approximately 504 tons.

Upon completion of residue removal and FabriForm removal the impoundment retained a portion of its clay liner. A series of conducted on the liner to determine tests concentration to be encapsulated beneath the replacement tank. Appendix B presents the sample locations and test results from this effort. The results demonstrate that the residue was effectively removed prior to initiation of tank construction. concentration of five indicator compounds in the soil at final grades was in the part per million range, demonstrating over 99.9% reduction from pre-closure concentrations.

Equipment used during construction included earth moving equipment, pile drivers, trucks, and steel sheeting. This equipment was rinsed and then steam cleaned to remove construction area residues. Prior to leaving the site the equipment was wipe tested using procedures presented in Appendix C. The results of the testing, presented in Appendix C, demonstrated that the equipment was decontaminated in accordance with the approved closure Plan prior to leaving the construction area.



An asphalt pavement storage area was constructed as part of the closure program. The storage area was used to store soil from the impoundment area during the construction of the replacement tank. The stored soils were used to backfill against the concrete tank walls. When the asphalt area was empty it was washed down to remove residual soils. A wipe sample was collected and analyzed for selected parameters. The results of that sampling and analyses are presented in Appendix C. These results demonstrate that the closure was completed in accordance with the approved Closure Plan.

2.03 Cover Installation

A portion of the area occupied by the surface impoundment is now occupied by a smaller tank system. The remaining area was backfilled with soil from the excavation for the tank. The placed backfill was overlain by a clay cap system which was covered by asphalt.

The clay used to construct the clay cover was obtained from Campbell Sand and Gravel. Appendix D presents the results of testing conducted on the clay prior to selection for use. The results demonstrate that the clay met the specifications within the approved Closure Plan.

Prior to installation of the clay the soil backfill was compacted. Appendix E presents the results of testing done on the compacted soil. Subsequent to clay compaction samples were collected to demonstrate compliance with the approved Closure



Plan. The results presented in Appendix F demonstrate that the installed clay met the specifications contained in the approved Closure Plan.

Overlying the clay layer is a granular subbase for the asphalt cover. Appendix G presents quality control data on the granular base. The data demonstrate compliance with the approved Closure Plan.

Bound separately are as-built plans which document the construction of the replacement facility. Included within the as-built package are final grades and elevations for the concrete tank system and surrounding clay cap system. Visual inspection of the closed facility confirms that precipitation drains rapidly to the facilities sewer system in accordance with the approved Closure Plan.

2.04 Leachate Management

Rainfall and ground water infiltration to the construction area was pumped from the excavation to FMC's process waste water pretreatment facilities. The effluent was routed to the Patapsco waste water treatment facility for permitted discharge. This water management was in accordance with the approved Closure Plan.



2.05 Closure Certification

Certification of Closure is required under 40 CFR 265 and COMAR 10.51.05.07F. I am familiar with the closure actions and the approved Closure Plan and certify that closure of the Stormwater Retention Basin has been completed in accordance with the approved Closure Plan.

STENEN RESIDENCE


Steve R. Garver, P.E. Vice President New York State License No. 052526




IT IS A VIOLATION OF LAW FOR ANY PERSON.
UNLESS HE IS ACTING UNDER THE DIRECTION OF
ALCENSED PROFESSIONAL ENGINEER, TO ALTER
THIS DOCUMENT.









Appendices



APPENDIX A

STABILIZATION RESIDUE/FABRICATION DISPOSAL MANIFEST SUMMARY




APPENDIX A 1 of 3

APPENDIX A STABILIZED RESIDUE DISPOSAL MANIFEST SUMMARY(1)

	, ,	•			
DATE	MANIFEST NO.	MASS (lbs)			
11/22/87	90500	33380			
	90501	32560			
	90502	33980			
	90503	32380			
1/30/87	90504	25520			
•	90505	22840			
	90506	22120			
	90507	37140			
	90508	31840			
	90509	38960			
	90510	32940			
	90511	35440			
	90512	30180			
	90513	32040			
2/2/87	90514	38160			
	90515	41120			
	90516	39440			
r	90517	33500°			
	90518	36540			
	90519	41120			
	90520	37280			
	90521	35720			
	90522	22960			
	90523	37620			
	90524	37560			
L/4/87	90525	34080			
-, -, -,	90526	35360			
	90527	33220			
	90528	37960			
	90529	41940			
	90530	40020			
	90531	33800			
	90532	36780			
	90533	40560			
•	90534	42960			
	90535	42960			
	90536	42980			
	90537	38580			
	90538	41160			
	90539	40820			
	90540	42480			
	90541	39780			
	90542	41860			
	90543	38980			

APPENDIX A STABILIZED RESIDUE DISPOSAL MANIFEST SUMMARY(1) (continued)

	(00000200000)	
DATE	MANIFEST NO.	MASS (lbs)
12/8/87	90544	29200
	90545	34820
•	90546	40100
	90547	40400
	90548	39220
	90549	35220
1	90550	33580
	90551	36240
	90552	33360
•	90553	34080
12/9/87	90554	33060
12/10/87	90555	37820
19	90556	32920
•	90557	34480
	90558	35460
	90559	37260
	90560	38400
	90561	35980
	90562	34300
	90563	35180
	90564	34160
	90565	35660
12/14/87	90566	41320
,,,	90567	40720
	90568	41420
	90569	38140
	90570	40120
	90571	40100
.*	90572	39480
•	90573	36100
	90574	41780
	90575	35700
12/16/87	90576	35480
	90577	37680
	90578	42620
·	90579	41640
	90580	40700
	90581	46320
	90582	41000
	90583	42660
	90584	38700
	90585	377620
	90586	38640
	90587	38540
	90588	35460



APPENDIX A STABILIZED RESIDUE DISPOSAL MANIFEST SUMMARY(1) (continued)

DATE	MANIFEST NO.	MASS (lbs)
12/16/87	90589	35860
	90590	44760
,	90591	36020
•	90596	34760
	90597	34940
	90598	36820
	90599	40280
7/7/88	90103	43180
	90104	<u>44000</u>
TOTAL	•	3,632,120 (1816 tons) (2)

- Stabilized residue and FabriForm hauled to GSX Services of South Carolina Inc.Route #1, Pinewood, SC 29125, (803) 452-5003. SCD070375985 was 1816 tons. Approximate mass of components was as follows: residue (1097 tons), lime (215 tons), FabriForm and other concrete debris (504 tons).
- (2) Estimated components:
 residue 1097 tons
 lime 215 tons
 FabriForm and other concrete debris 504 tons



APPENDIX B

SOIL SAMPLE FIGURE/TEST RESULTS

Agricultural Chemical Group Baltimore

Interoffice

το File

Date December 31, 1987

From

A. P. Dean C. Dean

DWHorgan
BLJohansen

Subject


RETENTION BASIN SOIL SAMPLES - SOUTH QUADRANTS

CFKusiak DWPalmer AFShanta

On this date, in accordance with the requirements of the Stormwater Retention Basin Closure Plan, soil samples were collected by this writer in the two (2) south quadrants of the Basin following the Soil Testing Protocol - Section 02001 of the plan.

The attached print identifies sampling points. Only south quadrant sampling was conducted this date to accommodate construction schedules and sampling logistics. Sampling of the two (2) north quadrants will be conducted at a later date when construction grades in that area are achieved.

Samples were stored in a glass quart container, duly labeled and forwarded to the plant laboratory for the analyses set forth in the Protocol.







4	
	L

PLANT FMC	Arr. Time
Smpl. Date 12-31-87	Comp. Time
Smpl. Time_10: 30 Am	Shift
Rog'd By A.P. DEAN	
Smpl. ID_ <u>9E-9e;1</u>	Batch No. Derara Basi
Analyses Reg'd. Closu	
Spec 02001	



PLANT FINC	Arr. Time
Smpl. Date 12-31-87	Comp. Time
Smpl Time 10:45AM	Skifte
Regid By A.P BEAU	AU
Smpl. 10 SW So. 1	Batch No Reference BAGG
Analyses Regid_ Clos	ure Man





Interoffice

File

Date

January 13, 1988

From

A. P. Dean (in them

CC

DWHorgan BLJohansen CFKusiak DWPalmer AFShanta


Subject

RETENTION BASIN SOIL SAMPLE - NORTH WEST QUADRANT

On this date, in accordance with the requirements of the Stormwater Retention Basin Closure Plan, a soil sample was collected by this writer in the north west quadrant of the Basin following the Soil Testing Protocol - Section 02001 of the plan.

The attached print identifies sampling points. Only north west quadrant sampling was conducted this date to accommodate construction schedules and sampling logistics. Sampling of the north east quadrant will be conducted at a later date when construction grades in that area are achieved.

Samples were stored in a glass quart container, duly labeled and forwarded to the plant laboratory for the analyses set forth in the Protocol. Ms. Monica Miller of the Waste Management Administration, State Department of the Environment observed the sampling.



Interoffice

B. L. Johansen, A. F. Shanta

____January 13 , 1988

Date

A. P. Dean Cil Decin

CC

From

Subject

RETENTION BASIN SOIL SAMPLE - NORTHWEST QUADRANT

Accompanying this memorandum is a sample of the above referenced material which is submitted for analyses. As you know the Stormwater Retention Basin Closure Plan requires that soil samples be collected from four (4) quadrants of the former Basin when all wastes have been removed and construction grades for the new tank have been met.

At this time, only the northwest section of the construction area is ready; accordingly the sample is labeled NW (north west quadrant). The sample consists of five (5) core subsamples collected from the quadrant. One (1) composite sample is to be prepared from the five (5) subsamples.

The resultant composite is to be analyzed for the following materials which have been or could have been discharged to the Basin:

Orthonitrophenol
Orthonitrophenol methyl ether (Ether)
7-Hydrogen
7-Nitro
Carbon tetrachloride
Benzene
Monochlorobenzene
Chloroform
Toluene
Claisen
Isobutenyl

For your records, I have attached a copy of the specific Soil Testing Protocol - Section 02001 from the Closure Plan. Sampling of the remaining northeast quadrant will be done at a later date when construction grades in that area are achieved and pile installation is completed.

Agricultural Chemical Group Baltimore



Interoffice

To

File

Date

February 17, 1988

From

A. P. Dean Consider

DWHorgan BLJohansen

CFKusiak DWPalmer

AFShanta


Subject

RETENTION BASIN SOIL SAMPLE - NORTH EAST QUADRANT_


On this date, in accordance with the requirements of the Stormwater Retention Basin Closure Plan, a soil sample was collected by this writer in the north east quadrant of the Basin following the Soil Testing Protocol - Section 02001 of the plan.

The attached print identifies sampling points. Only north east quadrant sampling was conducted which concludes the State required soil sampling aspects ofthe project.


Samples were stored in a glass quart container, duly labeled and forwarded to the plant laboratory for the analyses set forth in the protocol.













Agricultural Chemical Group Baltimore



Interoffice

B. L. Johansen/A. F. Shanta

Date February 17, 1988

From

A. P. Dean O. No.

Subject

RETENTION BASIN SOIL SAMPLE - NORTHEAST QUADRANT

Accompanying this memorandum is a sample of the above referenced material which is submitted for analyses. As you know the Stormwater Retention Basin Closure Plan requires that soil samples be collected from four (4) quadrants of the former Basin when all wastes have been removed and construction grades for the new tank have been met.

With the collection of the northeast sample the required soil testing of the Retention Basin is concluded. The sample consists of (5) core subsamples collected from the quadrant. One (1) composite sample is to be prepared from the five (5) subsamples.

The resultant composite is to be analyzed for the following materials which have been or could have been discharged to the Basin:

Orthonitrophenol
Orthonitrophenol methyl ether (Ether)
7-Hydrogen
7-Nitro
Carbon tetrachloride
Benzene
Monochlorobenzene
Chloroform
Toluene
Claisen
Isobutenyl

For your records, I have attached a copy of the specific Soil Testing Protocol - Section 02001 from the Closure Plan.

~+

SOIL TESTING PROTOCOL - SECTION 02001

PART 1 - GENERAL

1.01 DESCRIPTION

- A. Work Specified
 - 1. Testing of remaining soils for contamination from Stormwater Retention Basin contents.
- B. Related Work Specified Elsewhere
 - 1. Earthwork: Section 02000
 - 2. Selected Fill: Section 02002
 - 3. Solidification and Removal of Accumulated Sludge: Section 02003
 - 4. Cover Materials and Installation: Section 02004
 - 5. Bituminous Concrete Pavements: Section 02005

PART 2 - EXECUTION

2.01 SAMPLING .

A. Sample Collection

- 1. The area located under the proposed 110 x 110 foot tank will be divided into four quadrants subsequent to excavation to construction required elevations.
- 2. Five (5) samples shall be collected from each quadrant: one from the center of each quadrant, and four at a distance of 10 feet from the center in each of four compass direction using 3/4 inch diameter Lexan tubing.
- 3. The samples shall be collected by driving the Lexan $^{\rm R}$ tube to a depth of 3 inches ± 0.5 inches and withdrawing the tubing.
- 4. One (1) composite sample will be prepared for each quadrant from the five (5) subsamples. The composite samples will be stored in a glass container which will be labeled as to sample location, date and sampler.

SOIL TESTING PROTOCOL - SECTION 02001

B. Sample Testing

1. The four composite samples will be submitted to a laboratory for analyses. The analytical program will include the following substances which have been or could have been discharged to the retention basin:

Orthonitrophenol
Orthonitrophenol methyl ether (Ether)
7-Hydrogen
7-Nitro
Carbon tetrachloride
Benzene
Monochlorobenzene
Chloroform
Toluene
Claisen
Isobutenyl

- END OF SECTION -

dumind of A State 10(8/2)



Interoffice

To B. L. Johansen, A. F. Shanta

Date December 31, 1987

CC

From

A. P. Dean Q.P. Juan

Subject

RETENTION BASIN SOIL SAMPLES - SOUTH QUADRANTS

Accompanying this memorandum are two (2) samples of the above referenced material which are submitted for analyses. As you know the Stormwater Retention Basin Closure Plan requires that soil samples be collected from four (4) quadrants of the former Basin when all wastes have been removed and construction grades for the new tank have been met.

At this time, only the south section of the construction area is ready; accordingly the two (2) samples are labeled SW (south west quadrant) and SE (south east quadrant). Each of the two (2) samples consists of five (5) core subsamples collected from the respective quadrant. One (1) composite sample is to be prepared for each quadrant from the five (5) subsamples.

The two (2) resultant composites are to be analyzed for the following materials which have been or could have been discharged to the Basin:

Orthonitrophenol
Orthonitrophenol methyl ether (Ether)
7-Hydrogen
7-Nitro
Carbon tetrachloride
Benzene
Monochlorobenzene
Chloroform
Toluene
Claisen
Isobutenyl

For your records, I have attached a copy of the specific Soil Testing Protocol - Section 02001 from the Closure Plan. Sampling of the two (2) north quadrants will be done in early January 1988 when construction grades in that area are achieved.

Interoffice

To A. P. Dean

Date January 29, 1988

From

A. F. Shanta

DWPalmer
DWHorgan

Subject

RETENTION POND CLOSING ANALYSES

The samples of soil that you took for the retention pond closing have been analyzed. Three samples were received labeled as follows:

SW soil 12/31/87 at 1045 SE soil 12/31/87 at 1030 NW soil 1/13/88 at 1350

Upon receipt the samples were refrigerated at 4°C. Before analysis, the soil in the five Lucite tubes comprising each sample were blended together. Portions of the blend were used for the analyses. The specified volatile components were determined by GC/MS using a purge and trap technique and the semi-volatile materials, after extraction, using GC ESTD (ref. FMC Methods GW-1, GW-7 and P-100). Detection limits were approximately 0.1 ppm and 10 ppm respectively for the volatiles and semi-volatiles. Results for the various parameters are given below:

,	Amo	unt in	ppm
Component	<u>SW</u>	<u>SE</u>	NW
Benzene	ND	ND	ND
Toluene	ND	ND	ND
Chloroform	ND	ND	ND
Chlorobenzene	0.2	2.1	0.1
Carbontetrachloride	ND	ND	ND
7-hydrogen	19	20	12
ONP	ND	ND	ND
Claisen	ND	14	22
Isobutenyl	ND	ND	ND
ONPME	162	253	175
7-nitro	44	49	36

elr

Agricultural Chemical Group Baltimore

APPENDIX B Orls of 15 Reof

Interoffice

To. A. P. Dean

Date February 23, 1988

From

M. L. Schrock

DWPalmer DWPalmer DWHorgan AFShanta

Subject

RETENTION POND CLOSING ANALYSIS

The final soil sample for the retention pond closure plan was taken and labelled NE Soil February 17, 1988 @ 0930. Please refer to your memo from A. F. Shanta dated January 29, 1988 and titled the same as this one for the methods of analysis used. The detection limits were approximately the same as before; 0.1ppm and 10ppm respectively for the volatiles and semi-volatiles with the results given below.

Component	Amount in ppm
Benzene	ND
Toluene	ND
Chloroform	ND
Chlorobenzene	ND
Carbon tetrachloride	ND
7-hydrogen	25
ONP	ND
Claisen	20
Isobutenyl	10
ONPME	301
7-nitro	62

elr



APPENDIX C

DECONTAMINATION WIPE TEST RESULTS

APPENDIX C

FMC CORPORATION
Agricultural Chemical Group
Baltimore, Maryland

Wipe Sampling Procedure

Discussion

Wipe testing is an indirect measure of the hazards encountered from skin contact with chemicals. If enough sites are chosen for wiping, the body of data accumulated indicates the general level of contamination. The amount of chemicals found during wipe sampling is dependent upon the nature of the surface, the desorbing liquid, the size of the area wiped, the original chemical deposition, and many other factors. This method provides for consistency in sampling, thereby reducing the number of variables present in this type of analysis. This method is consistent with the ACG method prepared by T. J. Clark.

- Analytes Any chemical that comes in contact with work surfaces, and leaves a non-volatile residue. This includes, but is not limited to, Ethion® and Pounce®.
- Matrix Any work surface where chemical residues exist. Typical areas may be valve handles, desk tops, hand rails, eating areas, door handles, and hands.
- Procedure Wiping Surface with a Kim-Wipe® moistened with isopropyl alcohol, desorbing with solvent, and gas chromatographic (GC) analysis.

Limit of Detectability

Variable, depending on the gas chromatograph and the detector. However, usually all components have a limit of detectability between 0.1 ug and 2.0 ug.

Apparatus

- Box of Kim-Wipe® Disposable Wipes" 5 x 8 1/2 inches.
- 2. Box of disposable plastic or neoprene gloves.
- 3. Bottle of rubbing alcohol (containing 70% isopropyl alcohol by volume in water).
- 4. Box of screw-cap glass vials with teflon cap liner for holding "wipe" samples for analysis in the laboratory.
- 5. Labels and tape.

APPENDIX C Oppose 17

Reagents

- 1. All chemicals must be A.C.S. reagent grade quality or better.
- 2. Isopropyl alcohol, A.C.S. reagent grade; V.W.R. catalogue #JT-9080-3.

Procedure

- 1. Dilute reagent grade isopropyl alcohol to 70% with distilled water. Mix well.
- 2. Mark off an area of 100 square centimeters with tape. This is the usual size of an area that is wiped. For areas that are not flat, such as door handles, the entire area is wiped.
- 3. Wear clean disposable gloves whenever taking "wipe" samples. This practice avoids contamination of the "Kim-Wipe®" by the hand and prevents skin contact with any toxic substances.
- 4. Remove a "Kim-Wipe®" tissue and fold the completely open tissue in half three times.
- 5. For WET "wipe" samples, add approximately 20 drops of the 70% isopropyl alcohol solution to the folded "Kim-Wipe®".
- 6. Go to the sample location and wipe the entire area with the "Kim-Wipe®". Wipe the surface firmly and completely, but not with sufficient hand pressure to damage the "Kim-Wipe®".
- 7. Fold the dirty side of the "Kim-Wipe®" tissue inward and wipe the same surface again.
- 8. Fold the dirty side inward and wipe the same surface a third time.
- 9. Fold the dirty side inward once again and insert it into the mouth of the glass vial. Place the cap on the vial, and mark the number or identity of the sample on the outside.
- 10. Wipe gloves clean after taking each sample with a clean paper towel moistened with water or isopropyl alcohol. It is suggested that gloves be changed or discarded after taking "wipe" samples in heavily contaminated areas where deposits are easily removed, or after every 10 "wipe" samples have been taken.

APPENDIX F

COMPACTED CLAY TEST RESULTS

APPENDIX F File 10.6.0



Professional Service Industries, Inc. PTL Division

REPORT OF INSPECTION SERVICES

ED FOR: FMC

Agricultural Chemical Group 1701 E. Patapsco Avenue

Box 1616

Baltimore, Maryland 21203

Attn: Mr. Clem Kusiak

July 15, 1988

PROJECT: FMC

Retention Pond

Baltimore, Maryland

P. O. No. 058940

OUR REPORT NO.:

427-80004-095

MARKS:

SUMMARY OF INSPECTION

As requested, a PSI representative was on site between 10:15 am and 11:15 am to monitor and test fill placements in area around the west, north, and east side 10' off the pond.

These services were performed on a full-time basis.

CONDITIONS REQUIRING CORRECTION - CORRECTIVE ACTION TAKEN

Attachments: Field Density Tests Report

Sketch

Respectfully submitted, Professional Service Industries, Inc.



Proposional Service Industries, Inc. PTL Division

FIELD DENSITY TESTS

Project Name: FMC RETENTION POND Client's Name: FMC '' General Contractor: BON CIOVANNI Excavator: BON CIOVANNI									PSI Job No.: 427- 80004 Client Job No.: Date: 7-15-88 Weather: 50004 Temp. (°F): 95			
TEST NO.	MOISTURE (%)	DRY DENSITY (PCF)	PROCTOR NO.		CTOR_	PASS	FAIL	**	ELEVATION BELOW FINISH GRADE (FT.)	LOCATION GRID COORDINATES OR ROADWAY STATION RETENTION		
<i>1</i> 2	16.5 14.2	94.7	J	70	10-1 90-7	/			0	10'1 ALDING HIEST SIDE 10'1 20'N From NE CONNER 10' F 10'N From SE COMEV		
3	17.8	96.8			91.6	/			<u> </u>	10' 16 10'N FICH SE COME		
•				V			·					
		ļ ·										
Compaction Ed Smooth Steel D Vibratory Plate	Orum 🗆	Sheepsid Jumping Jac	oot 🗆 k 🗖	Walk	kicot 🖸 Behind S	Steel Dr	um 🛚	bber – tire	Other :			
(1) Test Location (2) Depth Or Ele (3) Test Conduct * Proctor No. Remarks:	v. Of Test Establi	Ished By: Surve e Basis () ensity (PCF)		Gr Basis 🛭				eation Estimation Of Procto		actor contractor contractor		
Technician:			Date:	7-	15 - CC			Approve	d:	Field Copy Given To Client Yes No		




Professional Service Industries, Inc. PTL Division

3 OI 608 BARKWUUD COURT LINTHICUM, MARYLAMD 21090 TEL: 301-789-3224

or 3

Page



Lab No.

PTL-II Order No.

ketch No



Professional Service Industries, Inc. PTL Division

REPORT OF INSPECTION SERVICES

TESTED FOR: FMC

Agricultural Chemical Group 1701 E. Patapsco Avenue

Box 1616

Baltimore, Maryland 21203

Attn: Mr. Clem Kusiak

June 28, 1988

PROJECT:

Retention Pond

Baltimore, Maryland

P. O. No.: 058940

OUR REPORT NO.:

427-80004-091

LARKS:

DATE:

SUMMARY OF INSPECTION

As requested, a PSI representative was on site between 11:30 am and 3:30 pm to monitor and test fill placements in area around retention pond 50' surrounding.

These services were performed on a full-time basis.

CONDITIONS REQUIRING CORRECTION - CORRECTIVE ACTION TAKEN

During our visit non-compliances were encountered regarding fill placements.

These non-compliances along with corrective measures are listed in the attached test reports.

Attachments:

Field Density Tests Report

Sketch

Distribution: Client (1)

Respectfully submitted, Professional Service Industries, Inc.



FILED DENSITY TESTS

Project Name:									PSI Job No.: 427- 8004 24 Client Job No.: Date: 6/28/88 Weather: 50010 7 Temp. (°F): 80			
TEST NO.	MOISTURE	DRY DENSITY (PCF)	PROCTOR NO.	1 (SE DE LA CETUAL	PASS	FAIL	**	ELEVATI BELOW FINISH GRADI (FT.)	V LOCATION GRID COORDINATES E OR ROADWAY STATION		
,	20 4	75. 1	1	40	91.4	1			- 14"	80'SW From NOLTH COLNER		
	17.0	737			, 1.1		/	ict		30'w 40's		
ち	1176	7. 1			803		/	ART		10' W "		
21	17.0	98.6			73.1	1				100/5 11 11 11		
	٤.	47 2			92.3	1				70'5 30'€ 11 11		
'erce	14.5	100.8			75.6	/		· .		40'S 30'E		
.,,	16.3	95 8			10.8	1		R-2		30'4 40'5 1'"		
8	15.01	963			91.3	1		R-3		10'W 11 11 "		
ب	171	38.6						ART		10' 5 5' 11 11 11		
; C)	18.7	43.1%		V						20'5 30'Z		
Compaction (Smooth Steel Vibratory Plan		t: Vibratory Sheepsfo Jumping Jack		Bric	y [] :klcot [] Behind S		-	ober – tir	ed 🗆 Other	•		
(2) Depth Or El (3) Test Condu	on Established By: lev. Of Test Establi cted On: Full Time	shed By: Survey a Basis □	Intermittent	Gr Basis □			E	ation d		Contractor Contra		
* Proctor No.	Maximum De		Opt. Moisture	(76)	<u>21</u>	Procto	<u>or m</u>	od Procid	<u>.</u>	Codes: (AR) - Area Re-Rolled (ART) - Area Re-Rolled & Re-Tested (R-X) - Retest Of Test No. X		
Remarks:	V4 T	(32)	-0-X	D. C. C.	<u> </u>	180	7,3	REKO	LLED	AND PASSED		
										(2. 2)		
Technician:	Druce	Can	_ Date:	6/.	25/8	Ý.	· · · · · ·	Approve	d:	Field Copy Given To Client Yes No		

APPENDIX 5 of 7



PTL Sivision

FIELD DENSITY TESTS

Project Name: FIL RETENSION POND Client's Name: FINC General Contractor: 1300 Ground 1991 Excavator: 500 Ground 1991										PSI Job No.: 427- 80004 34 Client Job No.: Date: 6/28/88 Weather: 50004 Temp. (°F): 80		
TEST NO.	MOISTURE	ORY OENSITY (PCF)	PROCTOR NO. #		F CTOR ACTUAL	PASS	FAIL	**	ELEVATION BELOW FINISH GRADE (FT.)	LOCATION GRID COORDINATES OR ROADWAY STATION		
1:	16-6	96.8	1	60	43.8	1	-	R-9	-1'	10'E S'N From THE NOITH		
12												
3												
1.7		• .				ļ !			,			
``					,							
•												
·												
14									,			
. •												
200										L		
nooth Steel bratory Plate		Sheepsfo Jumping Jack	oot @	Brick	denind S	iteel Dr	ım 🖸	ober – tire	Other:	actor O		
Depth Or Ele	n Established by: ev. Of Test Establis sted On: Full Time	shed By: Surve		Gra	de Slakes			stimation	/	Contractor		
Proctor No.	Maximum De		Opt. Moisture	(%)	<u>S1</u>	Procto	<u>or M</u>	od. Proctor	r ** Code	es: (AR) - Area Re-Rolled (ART) - Area Re-Rolled & Re-Tested (R-X) - Retest Of Test No. X		
emarks:	77	7										
echnician: Á	Dun Le	(i) an	Date:	./* /	./			Approve	d:	Field Copy Given To Client Yes No		


APPENUIX F



Professional Service Industries, Inc. PTL Division

808 BARKWOOD COURT LINTHICUM MARYLAND 21090 TEL:301-789-3234 FAX: 301-789-3233

FMC



ielch No

PTL-II Order No.

Lab No.

Page of __

APPENDIX G
COVER LAYER TEST RESULTS

Genstar Stone Products Company Executive Pleza IV Hunt Valley, Merylend 21031 Telephone (301) 628-4000



June 1, 1988

Baltimore Asphalt Paving Co. 1320 H. Monroe Street Baltimore, Maryland 21217 ATTN: John Elliott

> FMC - Retention Basin RE:

Gentlemen:

is to certify that the MD SHA-CR-6/GASB Crusher Run limestone as produced at our Texas, Maryland Quarry meets the requirements of the 1982 Maryland State Mighway Administration specifications under Section 903 and City of Baltimore specifications under Article 20.02.

The following gradation analysis is based on the average individual tests.

SIEVE_SIZE	2"	1 1/2"	- 44	#10	#200
Texus CR-6/GASD % Passing	100	99.5	36.2	25.8	5.9
SHA Tolerance Range Balto. City Spec.	100	90-100 100	29-49 25-55	15-45	2-12 0-12

This material complies with other specifications as set forth in the Maryland State Highway Administration and City of abrasion deleterious substances, regarding requirements soundness.

Respectfully submitted,

GENSTAR STONE PRODUCTS COMPANY

ed L. Oleckel se RORALD L. HECKEL

Hanager, Quality Control

Aggregates

RLN:kr

cc: J. Schwoerer

Exhibits







DEPARTMENT OF THE ENVIRONMENT

201 WEST PRESTON STREET • BALTIMORE, MARYLAND 21201
AREA CODE 301 • 225-5647

William Donald Schaefer Governor Martin W. Walsh, Jr. Secretary

October 6, 1987

CERTIFIED MAIL
Return Receipt Requested

Mr. Darryl Palmer
Environmental Manager
FMC Corporation
Agricultural Chemicals Group
1701 East Patapsco Avenue - Box 1616
Baltimore, Maryland 21203

Dear Mr. Palmer:

The Waste Management Administration (WMA) has received no further comment concerning the closure of the storm water Rentention Basin, since the hearing held on September 17, 1986. The WMA approves the closure plan as modified by a letter from FMC dated July 30, 1987 and a letter from WMA dated August 4, 1987. In accordance with the approved closure plan the post-closure permit application shall be submitted within 15 days and closure operations shall begin within 90 days upon your receipt of this letter.

As the public notice of the hearing for the closure was provided at the same time as the public notice for the incinerator permit, there will be one invoice for both notices. You should receive the invoice shortly, as it will be included with the incinerator permit.

If you have any questions concerning this matter, please contact Ms. Monica Miller of my staff at (301) 225-5701.

Sincerely,

Ronald Nelson, Director

Waste Management Administration

RN/lak

cc: Mr. V

Mr. William E. Chicca

Mr. Alvin Bowles

Mr. Charles Lewis

Mr. Reid Rosnick

Ms. Monica Miller

Mr. John Humphries



Important Note: DRY "wipe" samples are to be taken in the same way as 11. described above, with the omission of Step 5.

- The vials are to be returned to the laboratory for subsequent analysis. 12.
- A fresh piece of "Kim-Wipe®" that has not been used should be submitted to the 13. lab in a separate vial, for use as a blank.

Prepared by: Grand h. Johns Approved by: Mary 11.

Date:

Agricultural Chemical Group Baltimore

APPENDIX C 4 of 17

Interoffice

™ File

Dat Guly 20, 1987

FDHale-O'Brien & Gere

A. P. Dean

RETENTION BASIN CLOSURE PLAN - Wipe Test

Present closure plans call for the decontamination of equipment used in closure via water wash and steam cleaning. The State is suggesting that while acceptable, the decontamination requires verification by analytical, laboratory results.

For purposes of experimentation, wipe tests were conducted on hand rails at the Retention Basin to simulate "analytical work" following decontamination if the State insists on same.

Procedure/Methodology/Standards:

*Basis For Assessment

- (1) Evaluate Potential Exposure to humans
- (2) Max. allowable concentration based on:
 - (a) For materials intended for re-use use mammalian LD50
 - (b) Area of surface to which human could be exposed use "standard size" of 100 ft (surface area of 4-55 gal drums; customarily 4 drums/pallet)
 - (c) Avg. human body wgt. 170# (77 kg)

 - (d) Safety factor = 1/10 of LD₅₀(e) Contaminents to be evaluated individually

W = allowable wgt. of contaminant per 100cm²

 $w = 100 \text{cm}^2 \text{ X } 77 \text{ Kg X LD}_{50} \text{ X l} \div 100 \text{ft}^2 \text{ x } 929 \text{ cm}^2/\text{ft2 X l}$ = 0.0083 x LD₅₀

*Potential Materials For Analysis

•	110 ₅₀ x	.0083 X 1000 (mg-yag)	= Standard 2 = #g/100cm ²
ONP	3100		25730
Ether	872	·	7237
7-H	2745		22783
7-NO-	806		6690

Page 2


	<u>ld₅₀ x</u>	.0083 X 1000 (mq-4q)	, =	Standard 2 = Mg/100cm2
CC1 ₄	1770			14691
Benzene	3800			31540
MC Benzene	1540			12782
Chloroform	800			6640
Toluene	5000			41500
Claisen	2000/4000			16600/33200
Isobutenyl	1300/4436			10790/36819

*Sampling and Analysis

On July 14, 1987 at approximately 2:00PM this writer and K. H. Beach of the process lab conducted two wipe tests of the hand railing surrounding the north retention basin pump station (see photo); prior to sampling the railings were washed with warm water only and dried.

The top and bottom rail were both wiped with 70% isopropyl alcohol, diluted with 5 ml. methylene chloride and analized by gas chromatography for ten (10) hydroxy cmpds (including those hydroxy compounds noted above). With a detection limit of approximately 25µg/100cm₂ no hydroxy materials were found.

ct



WIFE TEST: 7/4/87 & 2:00 PM
Top & Bottom RML of 7-OH North Bet.
BASH Dir OLL WASHED OF WARM HED

7-OH RETENTION BASIN

DECONTAMINATION & WIPE TESTING*

MPLE I.D.	DATE/TIME	EQUIPMENT IDENTIFICATION	SAMPLED BY	RESULTS (µG/100CM ²)	ANALIZED BY	DECON.(Y or N
	18-5-21 8-30am	Liebherr 921 Excavator "buckes"	MHBeam	7-H ONPME CLAISEN ISOBUTENYL سائس عصد 7-NITRO	B.Johanson 12-8-87	KE2
	12-7-87 8:30AM	Liebhern 921 Excaunton LEFT TRACK	MH Bean	7-H ONPME CLAISEN ISOBUTENYL Win - COLL 7-NITRO	B. Ibasen 18-8-51	Y,gs
	12-9-87 2:50 PM 12-10-87 11 05 AM	J.E.McCAUSLAUB, Tuc "Whole of a Pump" # 4496 Pump Hena (M5-13)	ADDENU	7-H ONPME CLAISEN الله عصيد ISOBUTENYL 7-NITRO	B. Thruin	, V ^{az}
	12-2-87 2:50 PM	J.E. McCrushurs, Inc "Whole of a Purp" # 4450 PurpHeno	Ardenu	7-H ONPME CLAISEN ISOBUTENYL 7-NITRO	B. Johnson	القان
	12-22-87 8:55m	Mixing Dumpoter (lime)	V p Psvn	7-H ONPME CLAISEN w/m & caca_ ISOBUTENYL 7-NITRO	12-25-21	Y & 5

* INDUSTRIAL HYGIERE MANUAL Method *14-A 10-10-86

WPLE I.I	D. DATE/TIME	EQUIPMENT IDENTIFICATION	SAMPLED BY	RESULTS (p.G/100CM ²)	ANALIZED BY	DECON.(Y or N)
	78-55-51 MAZE:8	Mixing Dumpster (Sludge) #1285163	A.P Dean	7-H ONPME CLAISEN ISOBUTENYL 7-HITRO	13 Johann 12-22-97	Yes
	12-30-87 11:45/M	Mixing Dumpster (Studge) # 1285166	LASBEAU	7-H ONPME CLAISEN W/m seem ISOBUTENYL 7-NITRO	B. Johann 12-31-87	YE 2
•	12-30-87 11 50 NM	# 158=100 Wixing Dambeter	MSd4A	7-H ONPME CLAISEN ساست حوسد ISOBUTENYL 7-NITRO	3 Ibrases 12-51-87	Yes.
•	1-1-88 8:20AM	Komateu Excavator PC 200 LC "Bucket"	APDEA1)	7-H ONPME CLAISEN WIM SQUES ISOBUTENYL 7-NITRO	73. Johannan 1-11-99	YES
	1-7-88 8:30AM	Komatsu Londer WA-200 "Buchet"	linsdria	7-H ONPME CLAISEN ISOBUTENYL 7-NITRO	15 Johann	Yes
T.13.11	Sant Mine -	Management		I	l	

SAMPLE I.D.	DATE/TIME	EQUIPMENT IDENTIFICATION	SAMPLED BY	RESULTS (سG	/100CM ²)	ANALIZED BY	DECON.(Y or N)
	8:25WW	Decon Traver Clean Sins Locker Hanney & Front 200	MBd4A	7-H ONPME CLAISEN ISOBUTENYL 7-NITRO	Um squer	1/11/12 B 20801200	- AU maintained in in continuoted condition
	8:40 Am	Decon Tenden Clean Sinier Door Hool ? Light Switch	MPFEM	7-H ONPME CLAISEN ISOBUTENYL 7-NITRO	w/m sour	3. Johann 1/11/25	N
	1-7-88 8:45Am	DECON TRAILER Clean Sine Floor Area in Front of Lockers	WEGAA	7-H ONPME CLAISEN ISOBUTENYL 7-NITRO	ساین حصدد	1/11/88 B. Pyourn	16
	1-29-88 8:15 AM	C.J.LaugenFelder EUch D # ER 99 Interest bed of dump	Andro	7-H. ONPME CLAISEN ISOBUTENYL 7-NITRO	whin alone	Z J.P.z	Yes
	2- 4- 4A	C.J Laugenfalder Categollan D-5 # A-297 Left track	لامتشاط	7-H ONPME CLAISEN ISOBUTENYL 7-NITRO	w/m sour	B Johannes	Yes

DATE/TIME	EQUIPMENT IDENTIFICATION	SAMPLED BY	RESULTS (س	6/100CM ²)	ANALIZED BY	DECON.(Y or N)
2-8-88 2-54 P IN	C.J.Chirontolden Chlopaton 2-5 # 1 277 Frank C'ada	(w.e.f-14	7-H ONPME CLAISEN ISOBUTENYL 7-NITRO	W/m Speech	B. Idnamer 2-9-23	AE8
2.9-88 8:18PM	Corporation BEA MASTI Left draw:	hpbear)	7-H ONPME CLAISEN ISOBUTENYL 7-NITRO	Mm som	B. Tohonen 2-10-88	453
2-9-88 3:15PM	C.J Longefolder Cotagnilan 20 # A271 Front Block	Arbeau	7-H ONPME CLAISEN ISOBUTENYL 7-NITRO	w/m sper	3. Job onsun 2-10-88	Yer.
2-17-88 MACO P	C.J. Sangulyadur 3873 Crane - Track tread	ws24A	7-H ONPME CLAISEN ISOBUTENYL 7-NITRO	. W/m speek	E. J. Hamm 2-18-98	Yez
1:00 km 5-11-88	Dut Jean Etung pan of Catepullon D-5	AF Dens somple nearned from C7 Languelden to Machin	7-H ONPME CLAISEN ISOBUTENYL 7-NITRO	No Feat's For Hydroxy compiles gound potent, product	M. Schrock 2-17-88	Yês
	2-8-88 3:18PM 2-9-88 3:15PM 2-17-98 9:00AM	2-9-88 C. J. Langenglisher 2-9-88 C. J. Langenglisher 2-9-88 C. J. Langenglisher Let 4 ren:: Cotypilan D. 38 # A. 271 Cotypilan D. 38 # A. 271 Fraz Deade 2-17-88 C. J. Sangelgisher 3873 Cone- Track 4 read. 2-17-88 Dist Jean Stump pan of Categollan D-5	C. Thompsolver 200 Africal Chapter 2-4 Africal	2-8-89 2-9-88 2-9-88 3-18-PM Congestion D.S. # 1-277 Let trans. 2-9-88 2-9-88 C.J Langeldon Let trans. 2-9-88 C.J Langeldon Let trans. Congestion D.S. # A.Z. Congestion D.S. # A.Z. Congestion D.S. # A.Z. Front Books Congestion D.S. # A.Z. Front Books 2-17-88 Q.J. Sangeldolm 3873 Cone. Track tread 2-17-88 1:00 PM Chiepellon D-S Ditt Jum stump pan of Chiepellon D-S A. D. D. J. T. H. ONPME CLAISEN ISOBUTENYL 7-NITRO 7-H ONPME CLAISEN ISOBUTENYL 7-NITRO	2-9-88 2-9-89 2-	2-8-89 Colephan 1-5 # 1-277 Chiquina 1-5 # 1-277 Chiquina 1-5 # 1-277 Chiquina 1-5 # 1-277 Track track 2-9-88 Collegian 1-5 # 1-277 Chiquina 1-5 # 1-277 Alberta 7-H ONPME CLAISEN ISOBUTENYL 7-NITRO 7-H ONPME CLAISEN ISOBUTENYL 7

SAMPLED BY	RESULTS (pg/100CM ²)	ANALIZED BY	DECON.(Y or N)
Arbean	7-H ONPME CLAISEN ISOBUTENYL 7-NITRO	15:3080 m	ks
Cakahan	7-H ONPME CLAISEN ISOBUTENYL 7-NITRO	13 Johanso. 2-26-88	Yes
ARDEAU	7-H ONPME CLAISEN ISOBUTENYL 7-NITRO	B. John.	Yes
MasaM	7-H ONPME CLAISEN ISOBUTENYL 7-NITRO	13 Icharren 3-2-88	Yes
Magaa	7-H ONPME CLAISEN ISOBUTENYL 7-NITRO	18. Johannen 3-7-88	400
		ONPME Win squar CLAISEN ISOBUTENYL	ONPME Win squee 3-7-88 CLAISEN ISOBUTENYL

* INDUSTRIAL Hygiene MAU. Method # 14-A 100et 17

•				
ME EQUIPMENT IDENTIFICATI	ON SAMPLED BY	RESULTS (MG/100CM ²)	ANALIZED BY	DECON. (Y or N)
CIRM Bucket 18 34940	ADDEN)	7-H ONPME Whi squee CLAISEN ISOBUTENYL 7-NITRO	B.Johann 3.7-88	
Cement Buchet # 08-68 R 2390.01	Arben	7-H ONPME CLAISEN ISOBUTENYL 7-NITRO	78. IImm 3-7-89	
Bucyrus - Ere 350 Exeaunine TRACH	Mober	7-H ساس حوسد ONPME CLAISEN ISOBUTENYL 7-NITRO	B. Johanen 3-7-88	
Bucyrus- Erie 350 Exemuatur Bucket	tne <i>d-4</i> A	7-H ONPME CLAISEN ISOBUTENYL 7-NITRO	75. Johann 2-7-88	
1 1 1000 Transec	Arbens	7-H ONPME CLAISEN ISOBUTENYL 7-NITRO	15 John 3-9-88	
	Clam Bucket 28 34940 Clambut Bucket 408-68 R 2390-01 Bucyrus - Sere 350 Excavarian Treact Bucyrus - Erie 350 Sucavarian Bucyrus - Erie 350 Bucyrus - Erie 350 Bucket	CEMENT Bucket BUCYTUS - Serie 350 PRESENT TRACE BUCYTUS - Serie 350 APPEND APPEND Doon trade APPEND A	Clam Bucket 28 24940 ADDRN 1 CLAISEN ISOBUTENYL 7-HITRO CEMENT Bucket 20 08-68 R 7340.01 Bucyrus - Seve 350 Secondary TYRAR Bucyrus - Ceve 350 ADDRN 7-H ONPME CLAISEN ISOBUTENYL 7-NITRO TORAR Bucyrus - Ceve 350 ADDRN 7-H ONPME CLAISEN ISOBUTENYL 7-NITRO TORAR Bucyrus - Ceve 350 ADDRN 7-H ONPME CLAISEN ISOBUTENYL 7-NITRO ADDRN 7-H ONPME CLAISEN ISOBUTENYL 7-NITRO ADDRN 7-H ONPME CLAISEN ISOBUTENYL 7-NITRO ADDRN 7-H ONPME CLAISEN ISOBUTENYL 7-NITRO	Clam Bucket M 34940 APPENI T-H ONPME CLAISEN ISOBUTENYL 7-HITRO CEMENT Bucket M 08-69 R 2590-01 Bucket TRACE APPENI APPENI TONPME CLAISEN ISOBUTENYL 7-NITRO TRACE Bucket APPENI APPENI TONPME CLAISEN ISOBUTENYL 7-NITRO Tonpme CLAISEN ISOBUTENYL

INDUSTRIAL Hygiene MAUN Method # 14-A 11 of 17

PLE I.D.	DATE/TIME	EQUIPMENT IDENTIFICATION	SAMPLED BY	RESULTS (پرG/100CM ²)	ANALIZED BY (DECON.(Y or 1
,	3-7-88 1-50FM	Dean trailer	APbäau	7-H ONPME المرابعة CLAISEN ISOBUTENYL 7-NITRO	B. Johann 3-9-88	
	19-7-68 2:00Pm	Decontrolly clean will - dear knot- light switch (mule)	₩Ē dAA	7-H ONPME سانت عربید CLAISEN ISOBUTENYL 7-NITRO	7. Johnson 3-9-98	
· :	3-8-88 10:00m	Car Excavaron - 950 H-116 Blade	Arben	7-H ONPME CLAISEN ISOBUTENYL 7-NITRO	B. Johann 3-9-88	
	/4.09ww 3-8-88	Cherry Picker 34-256 Hook & Pulley	いゅうけイム	7-H ONPME CLAISEN ISOBUTENYL 7-NITRO	B. Johann 3-9-88	-
	3-8-65 10:00	I-13coms 20% sampled; all decoved A Samples	APD≥n.ı	7-H ONPME CLAISEN ISOBUTENYL 7-NITRO	73. Johnson 3-9-88	

WELDER IN HADING WAY

12 05 17

7-OH RETENTION BASIN

DECONTAMINATION & WIPE TESTING*

APLE I.D.	DATE/TIME	EQUIPMENT IDENTIFICATION	SAMPLED BY	ري RESULTS (پھر	100CM ²)	ANALIZED BY	DECON.(Y or N)
	3-10-88 1:10Pm	C.J.L. office haden Floor area	Arbana	7-H ONPME CLAISEN ISOBUTENYL 7-NITRO	whin secon	* B Johann 3-11-88	Res
	3-10-88 1:150m	CTL. office trade	APBeal	7-H ONPME CLAISEN ISOBUTENYL 7-NITRO	w/ in sque	B. Johann 3-11-88	yes
	g-30-88 9 aan	Spril Area Asphalt Pan SW-comuch	APDENI	7-H ONPME CLAISEN ISOBUTENYL 7-NITRO	w/m spiris	D. J. A. S. W.	پرمد
	8-30-89, 9 00 pm	Spoil Assa. Asphalt Pan SF-conver	Hrpsu1	7-H ONPME CLAISEN ISOBUTENYL 7-NITRO	دراس حودد	E John	4iv
	8-30-88	apoil Nor. Aspirall Dass	fi, cenn	7-H ONPME CLAISEN ISOBUTENYL 7-NITRO	w speek	15 Johann	uer.

INDUSTRIAL Hygiene MAN Method # 14-A APPENDIX

PLE I.D.	DATE/TIME	EQUIPMENT IDENTIFICATION	SAMPLED BY	RESULTS (مر) RESULTS)	ANALIZED BY	DECON.(Y or
	8-30-89 9-00AM	Spoil AREA Asphalt Pari	<i>t-1</i> t••)	7-H ONPME CLAISEN ISOBUTENYL 7-NITRO	B Johannen.	3 √ ~
				7-H ONPME CLAISEN ISOBUTENYL 7-NITRO		
				7-H ONPME CLAISEN ISOBUTENYL 7-NITRO		
				7-H ONPME CLAISEN ISOBUTENYL 7-NITRO		
	·			7-H ONPME CLAISEN ISOBUTENYL 7-NITRO		

7-OH RETENTION BASIN SHEET PILES Decontamination and Wipe Testing*

Sheet No.	Sample Date/Time	Sampled By	Results (ug/100 cm ²) 7-H -	Analized By	Decon. Yes/No
#15	6-3-88 2:45PM	LACUSA	ONPME - Wim Claisen - Spece Isobutenyl 7-Nitro	B. J. Danne	Y55
w 16	88-8-4 4-3-88	Al-Dan-I	7-H - ONPME - سالنس Claisen - هودن Isobutenyl 7-Nitro	B. Johann	Yङ्र
# \7	4-3-88 2:55AM	ARLEM	7-H - ONPME - Claisen - Isobutenyl 7-Nitro	15 Johann	الم.
*18	6-3-88 3:00PM	Al-Dean	7-H - ONPME - Claisen - Isobutenyl 7-Nitro	R Johann	Yes
		1	7-H - ONPME - Claisen - Isobutenyl 7-Nitro		

^{*}Industrial Hygiene Manual Method #14-A 10/10/86

7-OH RETENTION BASIN SHEET PILES Decontamination and Wipe Testing*

Sheet No.	Sample Date/Time	Sampled By	Results (ug/100 cm ²)	Anal i zed By	Decon. Yes/No
₩6 (2-26-98 5-26-98	Arbina	7-H - ONPME - Claisen - Isobutenyl 7-Nitro	e 18 Todaucea o	Y5c _
~ 81	6-1-88 9.00AM	Madad	7-H - ONPME - Claisen - سانس Isobutenyl sees 7-Nitro	B. Johnson	Y€r
* 85	86-1-5 MAZO:P	LNS01A	7-H - ONPME - Claisen - Isobutenyl 7-Nitro	B Iolmoun	Y=3
₹ 8 6	6-1-88 9:10 AM	4.h ben.)	7-H - ONPME - ساس Claisen - عودع Isobutenyl 7-Nitro	13. Johnween	Yes
#89	6-1-88 4:15 AM	Wegavy	7-H - ONPME - □ □ □ □ □ Claisen - □ □ □ □ □ □ □ □ □ □ □ □ □ □ □ □ □ □	13 Johnnes	4 €2

^{*}Industrial Hygiene Manual Method #14-A 10/10/86

7-OH RETENTION BASIN SHEET PILES Decontamination and Wipe Testing*

heet lo.	Sample Date/Time	Sampled By	Results (ug/100 cm ²)	Analized By	Decon. Yes/No
* 44	5-26-88 7:10Am	APISEAN	7-H - ONPME - Claisen - سانس Isobutenyl 7-Nitro	B. Tohanson	4es_
* 10	5-26-88 7:15 Am	Maga	7-H - ONPME - Claisen - w(~ Isobutenyl 7-Nitro	12 Johnston	Y65
- 49	5-26-88 7-20AM	Ahaau	7-H - ONPME - Claisen - wim Isobutenyl sceen 7-Nitro	12. J.A annu	Y=:
+ 45	5-26-88 7-25AM	LAGOL JA	7-H - ONPME - wjm Claisen - ≤eacs Isobutenyl 7-Nitro	13 Tamisen	Yes
# :57	5-26-8 \$ 5:15PM	LABOBAL	7-H - ONPME - سالم Claisen - Isobutenyl 7-Nitro	B. J.Anisin	Yes

^{*}Industrial Hygiene Manual Method #14-A 10/10/86



APPENDIX D

CLAY SOURCE TEST DATA

File 10.6.0



Professional Service Industries, PTL Division

June 23, 1988

FMC Agricultural Chemical Group 1701 East Patapsco Avenue Baltimore, Maryland 21226

Attention: Mr. Clem Kusiak

RE: Laboratory Test Results

Sample: Campbell Sand & Gravel

FMC Retention Pond Baltimore, Maryland

PSI No.: 427-80004-090

Gentlemen:

As requested, Professional Service Industries, Inc. performed laboratory tests on the above referenced materials. Test results are as follows:

Maximum Dry Density and Optimum Moisture

The maximum dry density and optimum moisture of the soil was determined per ASTM D-1557 Method A, test method for Moisture-Density Relations of Soils. The maximum dry density was determined to be 105.3 pounds per cubic foot. The optimum moisture was determined to be 16.0%.

Additional information of this test is enclosed.

Liquid Limit, Plastic Limit, and Plasticity Index

The liquid limit, plastic limit, and plasticity index of the soil was determined per ASTM D-4318-84. The soil was determined to have a liquid limit of 48, a plastic limit of 26, and a plasticity index of 22.

Per the unified Soil Classification System the material is considered to be a type of ML-CL material. A copy of the Unified Classification chart is enclosed for your information.

Phone: 301/789-3224

FMC June 23, 1988 Page 2 of 2

Permeability Test

The coefficient of permeability for this material at 95.3% compaction is 3.003 x 10⁻⁸ cm/sec. Material will need to be processed to break up material.

If you have any questions, feel free to contact me at your convenience.


Respectfully submitted,

Jeffrey A. Grueter Division Manager

JAG:sml


Enclosures






Distribution/Remarks

Client (1)



Manager



UNIFIED SOIL CLASSIFICATION SYSPERM 9

U.S. ARMY CORPS OF ENGINEERS - U.S. WATER AND POWER RESOURCES AGENCY - ASTM DEART

	lajor divi	sions	Group	Typical names		,	Laborat	ory class	ification	criter	ia .		
	r i		GW	Well-graded gravels, gravel- sand mixtures, little or no fines	$C_0 = \frac{O_{10}}{O_{10}}$ greater than 4; $C_0 = \frac{(O_{20})^3}{O_{10} \times O_{40}}$ between $C_0 = \frac{O_{10}}{O_{10}}$ presents than 4; $C_0 = \frac{(O_{20})^3}{O_{10} \times O_{40}}$ between $C_0 = \frac{O_{10}}{O_{10} \times O_{40}}$ between $C_0 = \frac{O_{10}}{$								
ve size)	ravels of coarse fraction is No. 4 sieve size)	Clean gravels (Little or no fines)	GP	Poorly graded gravels, gravel-sand mixtures, little or no fines	size), coerse	GM, G	Not meet	ing all grad	dation rec	anice me	nts-for	GW	
lo. 200 sie	than No. 200 Government than half larger than favel with fines (Appreciable nount of fines)		GM u	Silty gravels, gravel-sand-silt mixtures	Eurva. Io. 200-sieva	ine cases re	Atterburg line or P.	limits be	ow "A"	betwe	en 4 ar		rderline
ed soils ger than N			GC	Clayey gravels, gravel-sand- clay mixtures	n grein-size isiter than N	Borderline	Atterburg	cases requiring use of dual symbols					
Coarse-grained	ction is	Clean sands tite or no fines)	sw	Well-graded sands, gravelly sands, little or no fines	d gravel fron (fraction sm		$C_6 = \frac{D_{40}}{D_{10}}$ greater than 6; $C_6 =$			(D ₁₀) ¹ D ₁₀ ×O ₄₀ between 1 and 3			
5	Coarse ands of coarse fraction No. 4 sieve size)		SP	Poorly graded sands, gravelly sands, little or no fines	s of send en age of fines ollows:	604	Not mee	ing all gra	dation re	quireme	nts for	sw	
More than half	Sands (More than half of coarse fraction smaller than No. 4 sieve size)	ith fines ciable of fines!	SM u	Silty sands, sand-silt mixtures	Determine percentages of sand and gravel from grain-size curva. Depending on percentage of fines (fraction smaller than No. 200 sieve size), coarss-grained soils are classified as follows: Less than 5 per cent GM, GP, SW, 5 More than 12 per cent GM, GC, SM, 5 6 to 12 per cent		Atterbur line or P.	Limits plotting in hatched zone with P.I. between 4 and 7 are borderline cases					
	(More than half smaller than Sands with lines (Appreciable amount of fines)		sc	Clayey sands, sand-clay mixtures	Determin Dependir soils are	Atterburg limits above "A" Atterburg limits above "A" Ine with P.I. greater than 7					cuiring use of dual sym-		
ve)	Silts and clays Sults and clays		ML	Inorganic silts and very fine sands, rock flour, silty or clayey fine sands, or clayey tilts with slight plasticity	60		<u>, </u>						
			CL	Inorganic clays of low to medium plasticity, gravelly clays, sandy clays, silty clays, ean clays	50				-	СН			
ed soids smaller than No	l s	(Liquid)	OL	Organic silts and organic silty clays of low plasticity	city index								
Fine-grained soils		than 50)	мн	Inorganic silts, micaceous or diato- maceous fine sandy or silty soils, elastic silts	Plasticity 30				i ire	ОН	and	мн	
Find half of mate	is and Clay	(Liquid limit greater than	СН	Inorganic clays of high plasticity, fat clays	10	_	CL	X	_ _				
(More than h	is	(Liquid lin	ОН	Organic clays of medium to high plasticity, organic silts	اه	0 10	20	ML and 0			0 8	80 9	0 100
N N	Highly	soids	Pt	Peat and other highly organic soils				PLASTI					

^{*}Division of GM and SM groups into subdivisions of d and u are for roads and airfields only. Subdivision is based on Atterburg limits; suffix d used when L.L. is 28 or less and the P.I. is 6 or less; the suffix u used when L.L. is greater than 28. **Borderline classifications, used for soils possessing characteristics of two groups, are designated by combinations of group symbols. For example: GW-GC, well-graded gravel-sand mixture with clay binder.

Fines (silt or clay)**	Fines (silt or clay)**				Medium Sand	Coarse Sandi	Fine Gravel	Coarse Gravel	Coubles	
Sieve Sizes	-270	140		1 6	- 20 	<u> </u>	, × 	*	m 	

^{**}The L.L. and P.I. of "Silt" plot below the "A" line on the plasticity chart, Table 4, and the L.L. and P.I. for "Clay" plot above the "A" line.

Professional Service Industries, Inc. Pittsburgh Testing Laboratory Division

850 Poplar Street Pittsburgh, Pennsylvania 15220 412/922-4000

APPENDIX D

REPORT

No. 1

ORDER NO. 427-80004 DATE June 2, 1988

Client:

FMC Corporation

Report of:

Results of Permeability Test

Report to:

PSI - Baltimore

Project:

N/A

Sample Identification:

No. 1

Sample Represents:

Shale

Samples Submitted by:

PSI - Baltimore

PERMEABILITY TEST RESULTS

T.	Remold	led Data	•	Coefficient of Permeability
Sample No.	Dry Density (pcf)	Moisture Content (%)	Compaction (%)	(cm/sec)
1	100.4	17.2	95.3	3.003×10^{-8}

Note: Test made on material crushed thru a No. 4 sieve and remolded to 95% of the maximum dry density furnished by PSI - Baltimore.

Respectfully submitted,

PROFESSIONAL SERVICE INDUSTRIES, INC.
PITTSBURGH TESTING LABORATORY DIVISION
Geotechnical Services

ms



O'BRIEN & GERE

May 6, 1988

9.3.5

M.A. Bongiovanni, Inc. 1400 Jamesville Ave. P.O. Boy 147 - Colvin Station Syracuse, N.Y. 13205

Dear Mike:

Your letter dated May 3 submitted test results for cover material to be used around the Stormwater Retention Tank. The submission was in accordance with Contract C Section 2004 Part 2 2.01. The attached test report was reviewed relative to the specifications and the reported permeability was 8.395 x 10^{-8} cm/sec, slightly above the specification of 1 x 10^{-8} cm/sec. The clay tested will meet the objective of the cover system. Consequently, the tested clay for the clay cover specified in the Contract Documents is approved.

If you have any questions, please contact me at (315) 451-4700.

Very truly yours,

O'BRIEN AND GERE ENGINEERS, INC.

Frank Hale

Research Manager

cc: S.W. Anagnost

C.F. Kusiak

D.M. Gresko

5. Wescott

PGI A-100-17

AIDIX

m. A. Bonglovanni, Inc.

GENERAL CONTRACTOR

1400 JAMESVILLE AVE. P.O. BOX 147 - COLVIÑ STA. SYRACUSE, N.Y. 13205 315-475-9937 O'ERIEN & A.

.

May 3, 1988

O'Brien & Gere Engineers Attn: Don Gresko 1304 Buckley Road Syracuse, NY 13221

Dear Don:

Attached find two (2) copies of test results on our proposed clay cover material. The tests indicate compliance with specification on all items with the exception of the permeability factor.

Specs call for a maximum of 1 x 10^{-8} CM/SEC while our material is extremely close at 8.395 x 10^{-8} CM/SEC. We would think that this material still falls within the "clay" classification.

Anticipating a potential problem, we are arranging for tests to be run on a sample from another source (Campbells Sand & Gravel). However, these tests take approximately 3 - 4 weeks for results.

In light of this, we ask that the material from Jos. J. Hock's pit be accepted so that we can be assured of a source as the work is scheduled to begin June 9th, 1988.

If Campbells product has better factors, we will use that material if you desire. We just don't want to be caught short.

We would appreciate your consideration on this matter. Please let us know as soon as possible so we can plan accordingly.

Very truly yours,

M. A. BONGIOVANNI, INC.

Michael Bongiovánni

MB:dbl Enclosures



APPENDIX E

COMPACTED SOIL BACKFILL TEST RESULTS



Proposional Service industries, Inc. PTL Division

FIELD DENSITY TESTS

General Conti	ractor: TSO	(,,00,200) 1						Client Job Date:6	No.: 427- 90004 No.: No.: Solve Temp. (°F): 100
TEST NO	MOISTURE	ORY DENEITY (PCF)	PROCTOR NO.	PRO	OF OCTOR ACTUAL	PASS	FAIL .	**	ELEVATION BELOW FINISH GRADE (FT.)	LOCATION GRID COORDINATES OR ROADWAY STATION
1	14.7	1006	1	90	95.3	W	<u> </u>		6	20'W 5'A FISH THE NORTH COLUMN
2	136	110.7			157	/				
3	20.5	103.6			90.1	. /				30'1 50'0 11 11 11
7	14.3	112.2	•		3	/				80'W 10'N
\(\)	13.5	107.3			94.1	/				10'5 95'W 11 11 11
6	15.0	103.7	;		903	//	ļ			42 5 80'W 11 11 11
7	12.6	105.0		;	91.3	/	ļ			60/5 110 W
ર ે	15.6	1021		!	121 2		<u> </u>			85's 90'W 11 11
,	15.6	108.3	<u> </u>		14.1					10'E
10	11.4	114.2	đ	× .	39.2		<u> </u>		γ .	30's 40' E
Smooth Steel Vibratory Plat		Sheepsfo Jumping Jack	001 🗹	Brid Walk Control	ckfoot D Behind S Points D rade Stake	Steel Dr	rum [] Estim	ation (2)	Other:	actor ontractor
	Maximum De	Basis (Y	Intermitten Opt. Moistur 14, 5	8 (%)) <u>S</u> (d Proct		od Procto		s: (AR) - Area Re-Rolled (ART) - Area Re-Rolled & Re-Tested (R-X) - Retest Of Test No. X
										, Op.
•	D.	Ca		6-	22 -	84		Approve		Field Copy

PT Division FIELD DENSITY


FIELD DENSITY TESTS

Project Name:										No.: 427- 80004 3 4 No.: -22-88 SUNNY Temp. (°F): 180°
TEST NO.	MOIŠTURE (%)	ORY DENSITY (PCF)	PROCTOR NO.	PRO SPEC.	OF OCTOR ACTUAL	PASS	FAIL	**	ELEVATION BELOW FINISH GRADE (FT.)	LOCATION GRID COORDINATES OR ROADWAY STATION
11	145	106.4	: 1.	77					ව	60'S 10'E From THE NOITH COPER
!2	12.4	1137		· V.	18.7				0	80'5 35' 11 11 11
<u> </u>					 					
<u> </u>				 	 			,		
				.	<u> </u>					
Compaction E Smooth Steel (Vibratory Plate			001 2	Brid Walk	kleot 🗆	Steel Dr			ed 🗆 Other:	
(2) Depth Or Ele	n Established By: ev. Of Test Establi sted On: Full Time	shed By: Surve	•	Control Gr	Points ade Stake					actor Cl contractor Cl
* Proctor No.	Maximum De		Opt. Moisture	8 (%)	<u>\$</u> 1	O Proct	or <u>M</u>	Od Procto	<u>or</u> * ★ Code	s: (AR) - Area Re-Rolled (ART) - Area Re-Rolled & Re-Tested (R-X) - Retest Of Test No. X
110111011101										
Technician: 🔏	Bruce	lain	Date	6-	22-	81		Approve	ed:	Field Copy Given To Client Yes No C



806 Barkwood Court, Samur Of 3
Result
Linthicum, Maryland 21090
301/789-3224

FMC



Sketch No. PTL Order No. Lab No. Page 4 of 4



APPENDIX O

Agricultural Chemical Group 1701 East Patapsco Avenue Box 1616 Baltimore Maryland 21203 (301) 355 6400

January 3, 1985

Mr. Joseph S. Stang Department of Health and Mental Hygiene Office of Environmental Programs

Enforcement Division 201 W. Preston Street

Baltimore, Maryland 21201

RETURN RECEIPT REQUESTED

Dear Mr. Stang:

As discussed with you on December 24, 1984, the following information outlines the HCl spill incident that occurred at our plant December 22nd.

CERTIFIED MAIL

On 12/22/84 at 0300 hours the drain valves on a new HCl on-spec line that was rerouted two weeks ago were found to be open. At this time the line was in use for six hours and about 490 gallons of HCl spilled on the roadway and into the construction site northeast of Building 90. Investigation showed that HCl was started at 2100 hours on 12/21/84. Upon discovery, the spill area was thoroughly flushed with water with 50 percent of the flushing going directly to our sewer system to our wastewater treatment system. The remainder of the flush was contained in a plywood form in the construction site, and soda ash was spread over the area of the spill. After this, the area was pumped to our wastewater treatment system. This procedure was repeated several times until the water in the area had a pH level above 5.0.

Several actions have been implemented to prevent a recurrence of such an incident. Effective immediately, the line will be checked twice per shift when in use and reinforcement of SOP was made to operators to conduct outside checks of their entire work area within one hour of shift change. In addition, the HCl storage tank level indicators will be checked for calibration and a flow indicator with read out in the MAC plant control room will be installed in the HCl line at the storage tank area just before the line tee's off to tanks.


In addition to these corrective measures, our environmental department has reinforced to appropriate personnel/supervisors the need to call in a release of any controlled hazardous substance within one hour to the OEP enforcement division.

Should you have any questions or comments concerning this incident, please do not hesitate to call me.

Sincerely,

D. W. Palmer Environmental Manager

DWP:ct



4564-b

JAY 30, 1982

Agricultural Chemical Group 1701 East Patapsco Avenue Box 1616 Baltimore Maryland 21203 (301) 355 6400

21

June 20, 1985



Mr. Joseph S. Stang
Department of Health and Mental Hygiene
Office of Environmental Programs
Enforcement Division
201 West Preston Street
Baltimore, Maryland 21201

CERTIFIED MAIL
RETURN RECEIPT REQUESTED

Dear Mr. Stang:

As discussed with you on both June 19 and 20, 1985, the following information outlines the breakage of the HCl scrubber sewer line.

On June 19, 1985 at approximately 4:00 PM, it was noted that during the course of construction in the Plant 4 area, an underground terra-cotta pipe was accidentally broken. This pipe contains HCl contaminated water from the HCl scrubber bleed line. Since the pH is approximately 1.5, at a flow rate of approximately 2 GPM, the liquid is piped directly to the plant sewer system for treatment prior to discharge to the city sewer system.

Within a short time after notification was received, the area was flushed with fresh water for approximately 12 hours at a rate of 8 GPM. Due to this corrective action, the resulting pH was ~ 5 . All free liquid was pumped to a plant sewer for further treatment.

Temporarily, a chemical hose will be routed to a plant sewer until permanent repairs are completed.

If you have any questions concerning this incident, please do not hesitate to call.

Sincerely yours,

C. A. Shaheen

Environmental Engineer

CAS:ct

Agricultural Chemical Group 1701 East Patapsco Avenue Box 1616 Baltimore Maryland 21203 (301) 355 6400

July 12, 1985



Mr. Paul Thompson
Department of Health and Mental Hygiene
Office of Environmental Programs
Enforcement Division
201 W. Preston Street
Baltimore, Maryland 21201

CERTIFIED MAIL
RETURN RECEIPT REQUESTED

Re: Permit No. 80-DP-0499C

Dear Mr. Thompson:

As discussed in our phone conversation at 6:25 PM on July 10, 1985, the report on the 7/10 caustic spill incident is herein submitted. On July 10, 1985 at 6:00 PM while charging caustic to the DV acid chloride (FMC 30063) scrubber jet, a leak developed and resulted in a spill of approximately 25 gallons of caustic outside the process containment area. The wetted area was covered with sta-dri and subsequently shoveled into containers for later disposal. A sample of the outfall 002 effluent stream during the cleanup activity analyzed at a pH of 7.6. A grab sample at 9:00 AM on 7/11/85 yielded a 7.3 pH.

An investigation of the scrubber jet showed that a crack in the Haveg jet housing was the source of the leak. The scrubber jet system will not be used until a replacement or repaired jet is available and installed. Should you have any questions or comments concerning this incident, please do not hesitate to call me.

Sincerely,

D. W. Palmer

Environmental Manager

DWP:ct

Agricultural Chemical Group 1701 East Patapsco Avenue Box 1616 Baltimore Maryland 21203 (301) 355 6400

August 13, 1985

Mr. Joseph S. Stang
Department of Health and Mental Hygiene
Office of Environmental Programs
Enforcement Division
201 W. Preston Street
Baltimore, Maryland 21201

FMC

CERTIFIED MAIL
RETURN RECEIPT REQUESTED

Dear Mr. Stang:

As you requested, I am submitting the plan for reconstructing the Building 12 sump.

To date, this sump has been emptied and a 2 ft. depth of #6 stone was placed on the bottom. The walls have been water blasted and are to be sandblasted in preparation for an epoxy concrete lining. Prior to lining, the opening in the west wall will be plugged and sealed with concrete and then an additional 4 ft. depth of stone and a 1 ft. concrete pad will be installed to decrease the sump volume and improve maintainability. An east-west weir wall will be installed in this sump to allow one compartment to serve as a carbon-grit trap for the backflush water from our carbon system. Two self priming pumps operated via a low-high automatic level control system will be installed in the north section of the sump. The surface drain west of the railroad tracks will be renovated and remain connected to this sump. The area around this surface drain and the sump will be graded to allow runoff into the sump with no accumulation of rain water. The sump water will be pumped into the sewer system that goes to our settling basins and carbon treatment system. It is estimated that the sump repair itself will be completed by 11/1/85 and the pumps and transfer piping installation completed by 2/1/86. In the interim, the Building 12 sump will be kept emptied via a portable pump and/or steam syphon. I trust that this plan meets your approval and will keep you informed of any major changes or developments.

Also, no seepage into Stonehouse Cove from west of Building 12 has been observed since a former abandoned drain pipe in the vicinity of the surface drain was removed. A sample of the discolored gravel in this area was analyzed and determined to be 2-4 dinitro-6-sec-butylphenol. This material was removed, drummed and prepared for shipment to a secure chemical landfill.

Please call me if any comments or questions arise.

Sincerely,

R. T. Sebrosky

Environmental Engineer

RTS:ct

Agricultural Chemical Group 1701 East Patapsco Avenue Box 1616 Baltimore Maryland 21203 (301) 355 6400

December 26, 1985



FMC

Joseph Stang
State of Maryland
Department of Health and Mental Hygiene
Office of Environmental Programs
201 West Preston Street
Baltimore, Maryland 21201

CERTIFIED MAIL
RETURN RECEIPT REQUESTED

Dear Mr. Stang:

In accordance with the Baltimore facility's CHS Permit, I am following up my 11:30 A.M. telephone call to William Schmidt and Reid Rosnick (0.E.P. representatives) with this memo officially notifying your office of a release that occurred at this plant on December 23, 1985. At approximately 11:15 A.M., I was informed that on the north side of Patapsco Avenue (Pounce facility), some DV Ester (product) splashed onto the ground. After thoroughly investigating this incident, I determined the cause and volume of material involved.

A tank truck located in a concreted and diked containment area was being filled with product (DV Ester) - normal operating procedures were being observed. After filling was completed, the loading pump was shut off. Shortly there after, liquid began to leak from a teflon seal, located in the loading line. The liquid (DV Ester) drained onto the previously loaded tank truck - causing the material to splash and subsequently fall to the ground.

The total volume of material that was contained in the loading pipe was \sim seven gallons (7). I estimate, that \sim 1-2 gallon of DV Ester splashed onto the ground, while all remaining material was contained in a diked area. Absorbent was immediately placed on all free liquid, and shoveled into drums. All drummed material will be sent to a secure chemical landfill for disposal.

The loading line was then checked out to determine the cause of the teflon gasket failure. It was noted that apparently during mechanical assembly of this system, a metal backing plate (required to provide

Page 2

rigidity to teflon gaskets) was omitted - thus responsible for the gasket failure. This system will be repaired and checked before use is permitted.

If you have any additional questions, please contact me.


Sincerely,

C. A. Shaheen Environmental Engineer

CAS:ct

cc: DWPalmer RNMesiah - Phila. FSiwajek DCLewis

Agricultural Chemical Group 1701 East Patapsco Avenue Box 1616 Baltimore Maryland 21203 (301) 355 6400



JAN 16 1986

ENENT DIVISION

January 15, 1986

Joseph Stang
State of Maryland
Department of Health and Mental Hygiene
Office of Environmental Programs
201 West Preston Street
Baltimore, Maryland 21201

CERTIFIED MAIL
RETURN RECEIPT REQUESTED

Dear Mr. Stang:

On January 14, 1986, at approximately 12:45 PM, a small quantity of DV Ester (Product) was released outside of a containment area.

While attempting to straighten a pallet of 55 gallon steel drums containing DV Ester (Product), a forklift driver accidentally punctured one of the drums with one of the forks. Most of the liquid drained onto the macadam, and $\sim 1-3$ gallons drained onto a graveled area. The spill was responded to immediately. Oil-dry was immediately placed on all liquid, shoveled up and placed into drums. These drums of material were placed on a designated CHS storage area in preparation for shipment to a secure chemical landfill.

I telephoned the above information to Mr. Reid Rosnick, O.E.P., at approximately 1:00 PM in order to comply with the time constraint imposed by our CHS permit.

If you have any questions, please contact me.

Sincerely,

C. Q. Shakeen
C. A. Shaheen
Environmental Engineer

CAS:ct

Agricultural Chemical Group 1701 East Patapsco Avenue Box 1616 Baltimore Maryland 21203 (301) 355 6400 RECEIVED OF THE SAN 21 1986



January 15, 1986

Joseph S. Stang
Department of Health and Mental Hygiene
Office of Environmental Programs
Enforcement Division
201 W. Preston Street
Baltimore, Maryland 21201

CERTIFIED MAIL
RETURN RECEIPT REQUESTED

Re: FMC Corporation

NPDES Permit No. 80-DP-0499C (MD0000299C)

Dear Mr. Stang:

As discussed with you via telephone on January 8th, I am submitting a summary of the events concerning the high DV acid (FMC No. 30062) value obtained for our outfall 002 stream on January 3rd.

The composite outfall 002 sample for 1/3 analyzed 1.69 PPM DV acid. A grab resample taken 1/7 gave 1.04 PPM DV acid. Since some subsequent upstream samples (Bldg. 91 SE & Bldg. 91 SW corners) gave > 0.83 PPM DV acid we decided to hydroclean the B-91 sewer system including the piping to the outfall 002 sample station. All cleaning water from this operation was vacuumed into a tank truck for retreatment in the resin system. After the hydrocleaning operation, an outfall 002 grab and several upstream samples were taken and analyzed < 0.08 PPM DV acid. A composite outfall 002 sample taken 1/10 gave 0.080 PPM DV acid. Considering that no DV acid had been produced since mid-August and that the Bldg. 91 sewer system extending to the outfall 002 sample station was hydrocleaned in November, the source of the DV acid is puzzling. A possible explanation could be a pocket of contaminated dirt in the building trench system that was missed in the first hydrocleaning operation. To minimize chances of future outfall 002 DV acid excursions, we will implement a sampling program of an upstream source(s). Please contact me if there are any questions or comments concerning the above matter.

Sincerely,

R. T. Sebrosky

Environmental Engineer

RTS:ct

Agricultural Chemical Group 1701 East Patapsco Avenue Box 1616 Baltimore Maryland 21203 (301) 355 6400

FEB 29 1986



February 18, 1986

Joseph Stang State of Maryland Office of Environmental Programs 201 West Preston Street Baltimore, Maryland 21201

CERTIFIED MAIL RETURN RECEIPT REQUESTED

Dear Mr. Stang:

On February 13, 1986, you were informed by both Mr. Charles Lewis (0.E.P. 12:50 P.M.) and later by R. Sebrosky (FMC-2:08 P.M.), about two related releases that occurred at the FMC Baltimore plant on February 13. 1986.

At approximately 12:30 P.M. a tank of product (Sodium Sulfide) was overfilled due to an apparent failure of the tank's level indicator. At the time of overflow, the device indicated a level of 55%. Material flowed into a dike area and splashed onto a graveled area. I estimate \sim 30 gallons of material was not contained. Oil-dry was immediately thrown on all free liquid.

 \sim 12:45 P.M., the tank's fill line was steamed to remove all product, however, a gasket failure occurred at a flanged section of piping, resulting in a release of ~ 20 gallons of product. All product fell to a graveled surface.

The line was immediately isolated in order to begin clean up procedures. Oil-dry was placed on all free liquid to contain the material. The contaminated gravel from both of the above incidents was removed and will be disposed at a secure chemical landfill.

A follow-up investigation noted that the liquid in the upper half of the product tank was frozen (tank is not heated or insulated) causing the level indicator to malfunction. A modification to this level indicator system will be devised to insure this mishap does not reoccur.

If you have any questions, please contact me.

Sincerely.

C.Q Shahaen C. A. Shaheen Environmental Engineer

Agricultural Chemical Group 1701 East Patapsco Avenue Box 1616 Baltimore Maryland 21203 (301) 355 6400 ,,(

May 22, 1986

RECEIVED FMC

MAY 27 1986

ENFORCEMENT DIVISION

Joseph Stang
State of Maryland
Office of Environmental Programs
Department of Health and Mental Hygiene
201 West Preston Street
Baltimore, Maryland 21201

CERTIFIED MAIL
RETURN RECEIPT REQUESTED

Dear Mr. Stang:

On May 22, 1986 at ~11:30 A.M. Chemical Waste Management, Inc. (C.W.M.) personnel were loading copper sludge (a non-RCRA waste) from a waste tank. During this period, a gasket in C.W.M.'s trailer dome failed, resulting in a release of approximately 20 gallons of waste material. The material was released to a graveled area outside a concreted containment area.

Clean up and containment of the material began immediately. All contaminated dirt and gravel were removed and scheduled for shipment to a secure landfill.

The above information was telephoned to Ms. Debbie Ford, 0.E.P. at \sim 12:30 P.M.

If you have any questions, please contact me.

Sincerely,

C. a Shaleen

C. A. Shaheen

Environmental Engineer

Agricultural Chemical Group 1701 East Patapsco Avenue Box 1616 Baltimore Maryland 21203 (301) 355 6400

June 2, 1986



EMEDICEMENT DIVISION

Joseph S. Stang
Department of Health and Mental Hygiene
Office of Environmental Programs
Enforcement Division
201 West Preston Street
Baltimore, Maryland 21201

CERTIFIED MAIL
RETURN RECEIPT REQUESTED

Dear Mr. Stang:

On Monday, June 2, 1986 at approximately 6:30 AM, a railcar of 93% sulfuric acid was being unloaded. During this transfer operation, a stainless steel flex hose began to leak - resulting in a release of approximately 30-40 gallons of acid to the graveled ground. The transfer operation was immediately ceased. Containment and neutralization of the spill was begun immediately. Soda Ash was placed on all liquid in order to neutralize the material, while water was used to clean off the rail car.

After I was informed about this release, I contacted your office at approximately 9:10 AM.

Sincerely,

C. A. Shaheen
Environmental Engineer

Agricultural Chemical Group 1701 East Patapsco Avenue Box 1616 Baltimore Maryland 21203 301 355 6400

November 25, 1986



RECEIVED

DEC 1 1986

ENFORCEMENT DIVIN

Joseph S. Stang
Office of Environmental Programs
Department of Health and Mental Hygiene
201 West Preston Street
Baltimore, Maryland 21201

Dear Mr. Stang:

This letter shall serve as a follow-up to my telephone call to the Department on November 23, 1986 at 0240 hrs., and our telephone conversation on November 24, 1986 at 0830 hrs.

In the early morning of the twenty-third we were removing heavy oils from our 2nd waste water treatment basin with a portable pump and chemical hoses to an incinerator feed tank for subsequent incineration. The overall purpose of the operation is to remove all material from the basin to permit inspection during our present outage and efforts in this regard had been underway for several days without difficulty. The operation was to continue during the night shift and upon starting the pump the operator proceeded to the control room (approximately 50' away). to check the incinerator feed tank level. In doing so the operator quickly noticed that the oils were being pumped to the concrete road, asphalt sidewalk and gravel area adjacent to the control room due to a separation in the hose connections. The operation was stopped immediately, absorbant applied and cleanup initiated.

A total of seven (7) drums of gravel-absorbant material were cleaned up and will be disposed at an approved facility. The estimated 100 gallons or less of heavy oils became very viscous in the cool night temperature and were confined to an approximate 12' by 15' gravel area bordered by roads, sidewalks and tank dike walls.

Should you have any questions or require any additional information, please do not hesitate to call me.

Sincerely yours,


A. P. Dean

Environmental Engineer

APD:ct

Agricultural Chemical Group 1701 East Patapsco Avenue Box 1616 Baltimore Maryland 21203 301 355 6400

March 9, 1987



FINE PROPOSITION

Joseph Stang
State of Maryland
Office of Environmental Programs
201 West Preston Street
Baltimore, MD 21201

CERTIFIED MAIL
RETURN RECEIPT REQUESTED

Dear Mr. Stang:

On March 6, 1987 at approximately 2015 hours, a valve located on a caustic scrubber line, developed a leak. The resulting leak allowed 10 gallons of a 25% caustic solution to spill onto the ground.

Afer discovering the leak, the leak was stopped and the contaminated dirt removed.

The above information was called into Mr. Paul Thompson on March 9, 1987 at approximately 2025 hours.


If you have any questions, please contact me.

Sincerely,

C. A. Shaheen Environmental Engineer

Agricultural Chemical Group 1701 East Patapsco Avenue Box 1616 Baltimore Maryland 21203 301 355 6400

March 19, 1987



ENFORCEMENT DIVISION

FMC

Joseph S. Stang
Department of Health and Mental Hygiene
Office of Environmental Programs
Enforcement Division
201 West Preston Street
Baltimore, Maryland 21201

CERTIFIED MAIL
RETURN RECEIPT REQUESTED

Dear Mr. Stang:

On Saturday, March 13, 1987, I informed you that an overflow from MH-4 occurred. Upon further investigation, it was determined that seepage had occurred along our south shore line.

The seepage occurred when a salt solution was being pumped from the first wastewater basin to the nearby sewer. The sewer line backed up and seepage was noticed along the south shore line. When the seep was noted, use of the sewer was immediately discontinued.

This sewer system will remain out of service until a determination is made and identification of the problem is determined. Options for repair or abandonment will be made and corresponded to you.

A sample of the liquid was taken and analyzed for our NPDES permit parameters. The results were:

Parameter	Concentration (PPM)
Total Organic Carbon	320
Total Suspended Solids	62.0
Total Chromium	0.13
Total Copper	0.14
Total Zinc	0.04
Phenolics	7.0
011 and Grease	51.3
FMC 30077 (Prenol)	<0.01 (ND)
FMC 30098 (Step I Product)	< 0.01 (ND)
FMC 30099 (Step II Product)	0.1
FMC 39338 (Methyl DV Ester)	2.07
Carbon Tetrachloride	< 0.00001 (ND)

Joseph S. Stang

Page 2

If you have any questions, please contact me.

Sincerely,

Ca Shaheen

C. A. Shaheen Environmental Engineer

Agricultural Chemical Group 1701 East Patapsco Avenue Box 1616 Baltimore Maryland 21203 301 355 6400

March 30, 1987



Joseph S. Stang State of Maryland Office of Environmental Programs 201 W. Preston Street Baltimore, Maryland 21201

CERTIFIED MAIL RETURN RECEIPT REQUEST

Dear Mr. Stang:

On March 27, 1987, a process pipeline containing Sodium Sulfide solution (Bi-product) failed. Upon observing the leak, the line was immediately taken out of service. Approximately 10 gallons of material leaked to the adjacent graveled area. This gravel was removed and the area was flushed with water.

The above information was communicated to Ms. Ruth Schelhaus, Enforcement Division within I hour of the incident.

If you have any questions, please contact me.

Sincerely,

C.O Shinese

C. A. Shaheen Environnmental Engineer

CAS:ct

RECEIVED

MAR 1987

ENFORCEMENT DIVISION

Agricultural Chemical Group 1701 East Patapsco Avenue Box 1616 Baltimore Maryland 21203 301 355 6400

April 1, 1987



Joseph S. Stang State of Maryland Office of Environmental Programs 201 West Preston Street Baltimore, Maryland 21201

CERTIFIED MAIL
RETURN RECEIPT REQUESTED

Dear Mr. Stang:

On April 1, 1987 a railcar containing a 47% solution of Potassium Carbonate (raw material) was being unloaded. During this operation approximately 50 gallons of material vented from the top dip-tube. The venting was secured when observed, and immediately stopped. This material leaked to the adjacent graveled area beneath the railcar.

The contaminated area was immediately flushed with water in order to neutralize the material.

If you have any questions, please contact me.

Sincerely,

C. a Shekum

C. A. Shaheen Environmental Engineer

CAS:ct

RECEIVED

APR 3 1987

ENFORCEMENT DIVISION

Agricultural Chemical Group 1701 East Patapsco Avenue Box 1616 Baltimore Maryland 21203 301 355 6400

May 15, 1987



Joseph S. Stang
State of Maryland
Office of Environmental PRograms
201 West Preston Street
Baltimore, Maryland 21201

Dear Mr. Stang:

This letter is a follow-up to our telephone conversation of May 10, 1987 at approximately 7:00 PM, at which time I reported to you a leak of hydrochloric acid (HCl) from an elbow in an FRP line in a pipe rack to the gravel surface below. This line transfers HCl from a production area to storage, and flow was stopped immediately upon discovery.

The area of gravel affected was approximately 15 square feet, and we estimate the loss to be less than 100 gallons. The gravel area was neutralized with soda ash and flushed to our in-plant sewer system. Repairs to this line were completed on May 12, 1987, and service restored.

Should you have any comments or questions regarding this matter, please do not hesitate to call me.

Sincerely yours.

A. P. Dean

Sr. Environmental Engineer

APD:ct

cc: DWPalmer

DCLewis

Agricultural Chemical Group 1701 East Patapsco Avenue Box 1616 Baitimore Maryland 21203 301 355 6400

June 12, 1987



FMC

Joseph S. Stang
State of Maryland
Department of Health and Mental Hygiene
Office of Environmental Programs
201 West Preston Street
Baltimore, Maryland 21201

CERTIFIED MAIL
RETURN RECEIPT REQUESTED

Dear Mr. Stang:

On June 11, 1987 at approximately 11:00 AM, a pump was transferring sulfuric acid from a railcar to storage. The operator observed that acid was leaking from the seal. The transfer was immediately stopped. After the pump stopped, the seal failed, releasing ~5-10 gallons of material to the adjacent gravel. The leak was valved off, neutralizing material was placed on the acid and the affected area flushed with water.

The above information was provided to Ms. Diane Lewis of your office.

If you have any questions, please contact me.

Sincerely yours,

C. A. Shaheen
Environmental Engineer

CAS:ct

RECEIVED

JUN 13 1987

ENFORGEME IT DIVISION

Agricultural Chemical Group 1701 East Patapsco Avenue Box 1616 Baitimore Maryland 21203 301 355 6400

January 22, 1988



J. S. Stang
State of Maryland
Department of the Environmental
201 West Preston Street
Baltimore, Maryland 21201

CERTIFIED MAIL
RETURN RECEIPT REQUESTED

Dear Mr. Stang:

This is a follow-up to the conversation you had with Messrs. D. W. Palmer and R T. Sebrosky on 1/16/88 regarding the release of Hydroxylamine Sulfate (HAS) solution.

The following is a description of the events leading up to the release.

During the unloading of an HAS railcar into a storage tank, an operator observed that a remote tank level indicator did not rise as much as experience told him it should. This was reported to the operations crew and an immediate inspection of the tank farm area revealed a large leak from a pressure indicator gauge. The operator immediately closed a valve upstream of the gauge to stop the leak.

An inspection revealed that approximately 20,000 gallons of HAS solution leaked into the plant's wastewater system and onto the graveled area. It was later verified that approximately 6700 gallons actually leaked to the graveled area, and the remainder was contained in the plant waste water system. The contaminated gravel was removed and placed in a dumpster. This material will be disposed of at a secure chemical landfill.

An incident investigation determined that a small leak had begun on 1/15/88 when the diaphragm on the oil filled pressure gauge ruptured exposing mild steel internals to the corrosive HAS solution. The leak grew larger as corrosion of the non-stainless steel parts of the gauge occurred.

Corrective measures to prevent a recurrence of such an incident have been implemented and include; increased checking of remote tank farm areas, possible valving off of remote pressure indicator gauges when not in actual use, and close inspection of equipment and tanks before and after a bulk transfer.

If there are any questions or comments regarding this matter, please do not hesitate to contact me.

Sincerely,

C. A. Shaheen
Environmental Engineer

RECEIVED

HAT TODOES WASTE ENFORCEMENT TEAM

Agricultural Chemical Group 1701 East Patapsco Avenue Box 1616 Baltimore Maryland 21203 301 355 6400

February 26, 1988

FMC

Pec 3/1/588

Joseph S. Stang
Department of the Environment
Waste Management Administration
201 W. Preston Street
Baltimore, Maryland 21201

Dear Mr. Stang:

This letter is to follow-up my telephone conversation with Harold L. Dye of your office at 8:50 AM on February 22, 1988. Shortly before 8:00 AM on the twenty second, we experienced a release of material from a vessel in our 7-Hydroxy Plant IV process area. Over-pressurizing resulted in the escape of material, mainly methyl isobutyl ketone (MIBK), through the vessel's pressure relief device to the diked area surrounding the equipment. We estimate that aproximately 180-190 lbs. of the material reached the gravel, sidewalk and road immediately outside and east of the dike.

Cleanup was immediately initiated, and consisted of washing all exterior surfaces (dike walls, sidewalk, road), and picking up all affected gravel. The gravel has been placed in a dumpster for disposal in a secure landfill.

On February 23, 1988, an incident investigation was conducted at which time it was concluded that a faulty flow meter caused an excessive reactant addition rate to the vessel. The flow meter has been replaced, and with increase preventive maintenance and calibration we would not expect a recurrence.

Should you have any questions or require any further information do not hesitate to contact me.

Sincerely yours,

A. P. Dean

Environmental Engineer

APD:ct

cc: Harold L. Dye

Agricultural Chemical Group 1701 East Patapsco Avenue Box 1616 Baltimore Maryland 21203 (301) 355 6400 PROPERTY.

March 8, 1988

FMC

Joseph S. Stang
Department of the Environment
Waste Management Administration
201 W. Preston Street
Baltimore, MD 21201

CERTIFIED MAIL
RETURN RECEIPT REQUESTED

Dear Mr. Stang:

This letter is to follow up my telephone conversation with Jeff Smith of your office at approximately 7:15 PM on March 2, 1988. Earlier that day, at 4:29 PM, an aerosol was vented from a reactor relief valve in the 7-Hydroxy Plant IV process area after the reactor over pressurized. The aerosol carried no more than 50 gal of methyl isobutyl ketone (MIBK) out of the reactor, which was deposited within the diked area and on nearby gravel. The State Waste Management Administration was contacted at 5:13 PM.

The process was shut down and cleanup began immediately after the spill. Paved areas, such as dike walls and floors and sidewalks were washed. Affected gravel was collected and placed in a dumpster for disposal at a secure landfill.

An investigation of the incident concluded that a malfunctioned level indicator caused the reactor to be filled excessively during raw material addition. The indicator has been repaired and will be checked more frequently to prevent another occurrence.

If you have any questions or require further information, do not hesitate to contact me.

Sincerely,

D. W. Palmer Environmental Manager

DWP:ct

RECEIVED

MAR 11 1938

HSWMA ENFORCEMENT PROGRAM

Agricultural Chemical Group 1701 East Patapsco Avenue Box 1616 Baltimore Maryland 21203 (301) 355 6400

June 20, 1988



Joseph S. Stang
Department of the Environment
Waste Management Administration
201 W. Preston Street
Baltimore, MD 21201

CERTIFIED MAIL
RETURN RECEIPT REQUESTED

Dear Mr. Stang:

This letter is pursuant to my telephone conversation with Mr. Richard Johnson at 8:35 AM on June 17, 1988.

On June 17th at 7:50 AM, about 15 gallons of waste sodium sulfide solution sprayed from an overhead pipeline onto the gravel underneath. The leak occurred when a new gasket in a recently replaced section of the pipe failed. The leak was discovered immediately and the transfer pump was shut off.

The faulty gasket has been replaced and the other gaskets in the new pipe section have been inspected. The contaminated gravel was shoveled up and put into (12) 55-gallon drums. These will be sent to a hazardous waste landfill.

If you need any futher information, please feel free to call me.

Sincerely yours,

J. J. Giblin

Environmental Engineer

JJG:ct

RECEIVED

JUN 22 19.0

entous and engine and

Agricultural Chemical Group 1701 East Patapsco Avenue Box 1616 Baltimore Maryland 21203 (301) 355 6400





August 5, 1988

Joseph S. Stang
Department of the Environment
Waste Management Administration
201 W. Preston Street
Baltimore, MD 21201

CERTIFIED MAIL
RETURN RECEIPT REQUESTED

Dear Mr. Stang:

This letter is pursuant to my telephone conversation with Art O'Connell on August 4, 1988 at 11:25 A.M.

On August 4 at 10:40 AM a relief valve on a vent line to the scrubber in the DV Ester/Cypermethrin building opened and discharged about 200 cubic feet of gas containing about 100 ppm hydrogen cyanide to the atmosphere. The relief valve reseated after 10 minutes.

The relief valve opened because the vent line was overpressurized, which was caused when a process filter was being blown out with nitrogen while the scrubber column was simultaneously operating in a flooded state.

The flowrate of caustic solution to the column was adjusted to correct the flooded condition.

If you need any futher information, please contact me.

Sincerely,

J. J. Giblin

Environmental Engineer

AUG 8 1988

RECEIVED

JJG:ct

HSWMA ENFORCEMENT PROGRAM

Agricultural Chemical Group 1701 East Patapsco Avenue Box 1616 Baltimore Maryland 21203 (301) 355 6400



FMC

February 28, 1989

Carrol James Leizear Hazardous & Solid Waste Management Administration Department of the Environment 2500 Broening Highway Baltimore, Maryland 21224

Dear Mr. Leizear:

As a follow-up to your visit of Friday, February 24, 1989, the damaged drum of soda ash found on the Building 34 - RCRA pad was overpacked that same afternoon.

Also, to aid in your familiarization of FMC Baltimore, I have enclosed a plot plan which is a little better in quality and more up-to-date than the one you may now have.

Sincerely,

a.P. Lean

A. P. Dean Environmental Manager

cc: Mr. Joseph Stang

ENFORCE OF THE PROPERTY OF THE PARTY OF THE

Agricultural Chemical Group 1701 East Patapsco Avenue Box 1616 Baltimore Maryland 21203 (301) 355 6400



FMC

May 24, 1989

Mr. James Leizear
Maryland Department of the Environment
Hazardous and Solid Waste Management
Administration
2500 Broening Highway
Baltimore, Maryland 21224

CERTIFIED MAIL
RETURN RECEIPT REQUESTED

Dear Mr. Leizear:

This letter is pursuant to my phone conversation with you on May 24, 1989 at 10:45 AM to report an accidental release of methallyl chloride.

On May 24, 1989 at about 10:20 AM, a flange gasket in a pipeline containing methallyl chloride (MAC) in the Plant IV area failed, resulting in about 20 gallons of MAC spraying outside the containment area onto an adjacent sidewalk and gravel. The MAC line was immediately shut down. Maintenance has repaired the flange. Oil dry was applied to adsorb the spilled material and it and the contaminated gravel have been placed in drums and will be sent to a hazardous waste landfill. No injuries occurred from this incident.

If you have any questions, please feel free to call.

Sincerely, Siblin

John J. Giblin

Environmental Engineer


JJG:ct

RECEIVED

ે5

Agricultural Chemical Group 1701 East Patapsco Avenue Baitimore Maryland 21203 (301) 355 6400

Box 1616







June 5, 1989

HSWMA
ENFORCEMENT PROGRAM

Mr. James Leizear
Maryland Department of the Environment
Hazardous And Solid Waste
Management Administration
2500 Broening Highway
Baltimore, MD 21224

CERTIFIED MAIL
RETURN RECEIPT REQUESTED

Dear Mr. Leizear:

This letter is pursuant to our phone conversation on June 1st to report an accidental spill of sodium sulfide solution.

On June 1, 1989, at approximately 10:30 a.m., a railcar being loaded with sodium sulfide solution, began leaking around its bottom fittings. The operator working at the scene immediately ceased the loading process and obtained assistance. A containment basin was set up underneath the leak with plastic sheeting and sand bags. Some rags were stuffed in the leak, which slowed its rate to about 1/2 gpm. The spilled liquid collected in the temporary basin was pumped back into the railcar, while simultaneously the railcar was pumped back into a tank, T-9107, in Bldg. 6 where the sulfide solution was generated. The railcar was emptied about 9:00 pm that evening. No injuries were caused by the spill or its cleanup.

The operator at the scene when the leak occurred estimated that about 50 gallons of solution spilled before the leak was contained. The soil contaminated by the spill was left in place because removing it from underneath the tracks would be technically difficult and because most of the spill was likely collected by a french drain system underneath the rail siding and diverted it into the plant sewer system and wastewater treatment plant. Higher sulfide levels in the wastewater treatment system later that day confirmed this.

The solution which spilled contained 15-18% sodium sulfide at a pH of 13.3. It is a by-product of the Ethion process and is sold to a paper manufacturing company for its own use.



Agricultural Chemical Group 1701 East Patapsco Avenue Box 1616 Baltimore Maryland 21203 (301) 355 6400



FMC

October 3, 1988

Mr. Joseph S. Stang
Department of the Environment
Hazardous and Solid Waste Management
Administration
201 W. Preston Street
Baltimore, Maryland 21201

CERTIFIED MAIL
RETURN RECEIPT REQUESTED

Dear Mr. Stang:

This letter shall serve as the requested follow-up to your inspection of Wednesday, September 28, 1988, addressing the items which you identified and the efforts we intend to take to prevent any recurrence.

The containers adjacent to our old incinerator were sealed, labeled and moved to our permitted south waste storage area by September 29th. Ultimate disposition and disposal of these drums is presently being determined.

The drums found in Building 6 were all likewise relocated to our permitted north waste storage area on September 29th. The drums identified "Ethion..." are non-RCRA hazardous and most were actually in-process materials, stored in the building for recovery and further processing during our present Ethion campaign. The sulfide waste drums contained materials removed from a process tank and had been held in the building to decant water from the drums every few days. Laboratory work was completed on September 29th characterizing these drums as non-RCRA hazardous. Nevertheless, we will dispose of this material at only licensed facilities, as is our normal policy.

The two-drums found in poor condition on our south waste storage pad were repacked on the evening of September 28th and the drums found at the perimeter of this area moved the same evening. We have attempted to control the access to these storage areas so as to better manage waste shipments and housekeeping at the area. Obviously, better definition is required to preclude storage of materials immediately outside the area.

RECEIVED

GOT 11 1988

PRINTERS PROCESS



Page 2

Immediately following your inspection and again on September 30th, meetings were held with our unit and areas supervisors to review the circumstances which led to your findings, our regulatory obligations and procedures which we must employ to prevent any recurrences. I believe we have established a sound and credible regulatory history and have in place those standard operating procedures necessary to meet both the letter and intent of the law. Communicating and reaffirming these requirements and responding to those items you may request of us during inspections is critical in order to maintain this history.

During the first week of October we are developing the format of a training session which we intend to convey to all employees (and contractors) on the plant involved in our waste handling activities. Although this will duplicate our annual RCRA training it is clearly necessary. These sessions will cover waste identifications, labeling and dating, inspection procedures, storage requirements, procedures involved with the accumulation of wastes in production areas, obligations of contractors working for FMC contract administrators, etc. With the completion of the agenda all retraining will begin immediately and be documented and completed by early November.

We very much appreciate your return visit this week and our discussions which will improve this training and our understanding of this complex area. If you have any comments, questions or other recommendation on these issues please do not hesitate to contact me. Please be assured that your findings of last week will not be found again.

Sincerely,

A. Parker Dean

Environmental Manager

APD:ct



APPENDIX P

Revised: Nov. 1986



SECTION 3

Inventory of Known Hazardous Wastes

Generated by, or known to exist on the premises of, the Baltimore Plant



T-6405 TMOA WASJE

	5/14/84	5/15/84
Methyl Aceate	7.3 %	7.3 %
Methanol	58.3 %	60.3 %
Acetonitrile	6.0 %	6.1 %
TMOA	ND	ND
Trimethyl triazine	0.8 %	0.7 %
Chlorotoluene *	26.1 %	25.0 %
Chloroform *	40 ppm	45 ppm
Carbontetrachloride *	2243ppm	2317ppm
Benzene *	23 ppm	24 ppm
Toluene *	61 ppm	61 ppm
Chlorobenzene *	34 ppm	34 ppm
Methylenechloride *	ND	ND .

WASTE METHANOL

	5/14/84
Isoprene / Heptane	55 %
Methyl Acetate	1.4 %
Methanol	42 %
Methylenechloride *	28 ppm
Chloroform *	115 ppm
Carbontetrachloride *	5109 ppm
Benzene * ,	270 ppm
Toluene *	82 2 ppm
Chlorobenzene *	853 ppm



2ND BASIN OIL P-2208

	5/14/84	5/16/84
7-H	0.5 %	1.0 %
ONP	35.7 %	32.1 %
Claisen	1.2 %	0.3 %
Isobutenyl	19.9 %	19.0 %
ONPME	1.5 %	6.7 %
7-Nitro	40.5 %	36.9 %
Tars	4.8 %	5.0 %
2-chlorophenol *	2690ppm	2303ppm

3RD BASIN OIL P-1205

$(x_1, x_2, \dots, x_n) = y_1^2$	5/14/84	5/16/84
$(x,y) \in \mathbb{R}^{n \times n}$		
7-H	6.2 %	6.0 %
ONP	3.4 %	3.5 %
Claisen	4.7 %	4.5 %
Isobutenyl	4.6 %	4.5 %
ONPME	61.1 %	59.5 %
7-Nitro	11.7 %	12.1 %
Tars	4.3 %	5.0 %

CLAISEN TAR P-2235

	5/14/84	5/16/84
ONPME	4.3 %	52.1 %
Tars	5.8 %	29.4 %
2,4-Dinitrophenol*	ND	165 ppm
4-Nitrophenol *	ND	780 ppm

Indications from the analytical data are that the sample taken 5/14/84 is mostly oil diluent.

SUPER TAR P-2236

		5/14/84	5/16/84
ONPME	· · · · · · · · · · · · · · · · · · ·	15.8 %	34.9 %
Tars	•	55.8 %	44.0 %
2,4-Dinitroph	enol *	123 ppm	217 ppm
4-Nitrophenol	, *	840 ppm	992 ppm

Robert to strayouth



COOLING TWR SLUDGE

Components %

30-60 Algae Residue 1 Chromate ION 500 ppm Zinc ION Balance Water

Sample Method Frequency

Grab/1/Yr.

Test Method

1-M 1-M

7-HYDROXY TAR



Components %

Sample Method Frequency

Test Method

100

Grab/1/6 months

F-V-9



The residue of 7-Hydroxy distillation where the 7-hydroxy is manufactured from ONP consists of dimer, trimers, tetramers and higher numbers of repeating units of the following basic building blocks (monomeric units).

- (1) 2,2 Dimethyl 2,3 dihydrobenzofuranol
- (2) 2,2 Dimethyl 2,3 dihydrobenzofuran
- (3) Xylene
- (4) 2,2 Dimethyl 2,3 dihydro 7 amino benzofuran

90% of all tars analyzed are dimers and trimers of the 1st two compounds.

G.C. volatile compounds have been identified to a molecular weight of ~450. Non- G.C. volatile compounds are assumed to be tetramers, pentamers and higher number repeating units of rapidly diminishing concentration.

Two other tars of the 75% identifiable by gas chromatograph do not fit the above description. They are:

3% 2,2 - Dimethyl - 2,3 - dihydro - 3 - Neto benzofuranol

2% 2,2 - Dimethyl - 2,3 - dihydro - 3 - hydroxy benzofuranol

7-OH TAR PLANT # 1

	5/15/84	5/16/84	
7-0H	2.4 %	2.3 %	
Tars	51.2 %	46.6 %	

7-OH TAR PLANT # 3

	5/14/84	5/16/84
7-0H	2.2 %	5.2 %
Tare	85.1 %	84.6 %

AOOLL



MAC WASTE

	5/14/84 T-1141	5/16/84 P-1142
IB	0.2 %	0.2 %
TBC	0.04%	.04%
ICC	1.5 %	1.7 %
MAC	6.3 %	5.2 %
DCIB (1)	45.4 %	49.2 %
DCIB (2)	32.4 %	33.2 %
TCIB (3)	14.1 %	13.4 %

DCIB (1) = 1,2-dichloro-2-methylpropane or dichloroisobutane

DCIB (2) = 3-chloro-2-chloromethyl-1-propene and (cis/trans) 1-chloro-2-chloromethyl-1-propene

TCIB (3) = 1,2,3-trichloro-2-methylpropane

hailing

FMC Corporation subject _______ Proj. No. ______ Pege ______ of ____

By J. Lorde Date 1/2/16/5.

DC18(2)

2

3-chloro - 2 - chloro mathyl- 1- propene

,ce

>= el

(cis /mus) 1-chloro-2-chloromethyl-1-propene

DCIB(1)

Lu

1,2-Dichloro-2 methyl-propane

08209900



WASTE METHANOL

Sample Method Frequency


Test Method

65-75 MeOH Grab/1/6 month 2-4 TMOA

DVE-1

Components %

1-2 MeAc





Components %

10-30 FMC 30098 30-60 FMC 30085 10-15 TMOA Sample Method Frequency

Test Method

Grab/1/6 months

DVE-1



4/26/85 CAS

CHLOROACETYLENICS

Composition	90
DV Ester	30 - 33
Heptane	25 - 30
Chloroacetylenics	25 - 30
Methyl Benzoate	5 - 10



MDD003071875 CAS 12/28/83

C-1 Chemical and Physical Analysis (Update)

TMOA WASTE ORGANICS

2
30-3
30-3
12-1
5-7
1-2
1-2
5-6
1-2
1.0

RCRA Classification - D001 - Ignitable Liquid

التنزرج



MDD003071875

CAS 12/28/83

C-1 Chemical and Physical Analysis (Update) (continued)

TMOA - Waste Filter Cake

Composition	*
Ammonium Chloride	75-80
Sodium Chloride	15-18
0-Chlorotoluene	6-8
Methanol	1.0
Trimethyl O-Acetate	1.0
Acetonitrile	10 ppm - 12 ppm

RCRA Classification - D001 - Ignitable Solid

2 Jugar



DVE STEP III BOTTOMS

Components \$

10-20 FMC 39338 10-20 FMC 30094 10-20 Trichloroproducts of FMC 30094

5-10 Methyl 3 Benzene 2,2 dimethylcyclopropane carboxylate

Balance - polymers of FMC 39338

Sample Method Frequency

Grab/1/6 months

Test Method

DVE-3



STEP III HEAD CUT

Components \$

Sample Method Frequency

Test Method

40-50 FMC 39342

10-20 FMC 39338

10-15 Methyl Benzoate

25-40 FMC 39338 Analogs

Grab/1/6 months D

DVE-3



STEP II

Components \$

80-85 CC1₄ 10-12 MeOH, MeAc, Isoprene 0-5%Chloroform

TR - Methyl prenyl ether

TR - Chlorobenzene

Sample Method Frequency

Grab/1/6/months

Text Method

DVE-2



DV ESTER BRINE

Components \$		
10-15 NaCl .13 McOH .12 Heptane	٠	
.25 polymers 39338	of	FMC
39338 ≤100 ppm CC1 ₄		
Trace Na ₂ HPO ₄		
Balance - H ₂ 0		

Test Method	
1285	
54.6° =	
DVE-3	
WW-2 Standard Method 424	



SPENT CARBON

Components \$	Sample Method Frequency	Test Method
.15 CC1 ₄ .1-1 Heptane	Grab /1/6/month	DVE-2adapted
1-2 MeOH	Grab/1/6 month	•*
TR-FMC 30098		
" 39338	" "	WW-3 adapted
<i>u</i> 30099	11 11	
Balance Carbon		

COPPER SLUDGE



Components &	Sample Method Frequency	Test Method
10-20 Na ₂ SO ₄ 1-3 Mg(OH) ₂ , NaOH	Grab/1/6 month	FMC - P-100
1-10 CuO .13 Xylene 3-6 polymerized benzefuranels Ralance H-O		ASTM (D 1067) 31 FMC-M-1

BASIN SLUDGE

Components %

60-70 Water


12-18 7NO₂
10-15 Isobutenyl
1-5 Isobutyl
1-5 Inorganic Salts
Balance Polymerized Tars

Sample Method Frequency

Grab/1/Yr.

Test Method

P-100 adapted





SODIUM BROMIDE

Components \$

5-15 NailTA 25-35 NaBr 50-70 H₂O 50-75 ppm Ethion

Sample Method Frequency

Grab/1/6 month

Test Method

I⁻MC - 30.1 FMC - 30.7

FMC - 30.7



ASBESTOS INSULATION

Components &


100 Asbestos

Sample Method Frequency

Grab/l/Yr.

Test Method

ASTM (D-628) 33





7 NO₂ BOTTOMS

Components %

30-50 MgCl₂ 50-70 7 NO₂ .5-.8 ONP Sample Method Frequency

Grab/1/6/months

Test Method

Filtration F-II-B-8





Components &

90-95 Glass 5-10 Plastic Caps .5-1 Various DHS Sample Method Frequency

Grab/As required

Test Method

Source determined



7-NITRO SPILLAGE

Components %	Sample Method Frequency	Test Method
90-93 7NO ₂	Grab/1/6 months	
90-93 7NO ₂ 1-4 Claisen	11 11	F-IIB-8
1-4 Isobutenyl	11 11	**
0-1 ONP	11 11	11



BASIN LIQUID

Components %	,	Sample Method Frequency	Test Method
40-50 ONPME		Grab/l/Yr.	F-IIB-1
2-5 ONP	•	11 11	**
10-40 Water		11 11	. 11
10-20 7NO ₂ Tars	.7	11 11	11
10-20 Sand, Dirt, Carbon	٠,	· · · · · · · · · · · · · · · · · · ·	Filtration



ONP SPILLAGE

Components %

5-10 ONP 90-95 Dirt/Gravel Sample Method Frequency

Grab/As Required

Test Method

FRM-I-1 Filtration



P S SWEEPINGS

Components &

75-90 P2S5

10-25 Dirt/Sand

Sample Method Frequency

Grab/1/Yr.

Test Method

Monsanto #12,389 or Outside Lab Filtration



EMPTY POUNCE DRUMS

Components %

Sample Method Frequency

Test Method

Grab/As Required

Pounce - 1



ALLYL ALCOHOL/ETHER

Components &

80-95 Diallyl Ether 4-10 Allyl Alcohol remainder H₂O

Sample Method Frequency

1/trunsfer to incinerator

Test Method

G.C.



MONOMERS RESIDUE

Component %

Sample Method Frequency

Test Method

95 Diallyl Phthalate (DAP)

1/transfer to incinerator

FMC - 23 G.C.

95 Diallyl Isophthalate (DAIP)

95 Diallyl Malcate (DAM)

remainder DAP, DAIP, or DAM polymers



OIL B

Component \$

80-90 Dithioic esters remainder Dithioic salts

Sample Method Frequency

grab/as required

Test Method

FMC - 30.5



POUNCE ORGANICS

Component %

70-80 MeOH 10-20 n-Octane remainder H₂O + HCl Sample Method Frequency

l/transfer to incinerator

Test Method

FMC - Pounce - 7



CYPERMETHRIN STEP I WASTE

Components %

NaCl 10-15 MeOH 5-10 FMC 30062 800-1500 ppm FMC 39338 1300-2000 ppm Water - Balance

Sample Method/Frequency

Grab-1/campaign

Test Method

FMC - FRM - 40 G.C. A% FMC - CYP - 1 FMC - CYP - IV-B ASTM (D-2777) 31



CYPERMETHRIN STEP II WASTE

Components %

NaCl 3-6 Na₂SO₃ 10-15 Na₂SO₄ 1-2 NaOH 0-1 Heptane 30-50 DV Acid Chloride 1-5

Sample Method/Frequency

Grab-1/campaign

Test Method

FMC - FRM -40 Outside Lab Outside Lab FMC - 285 FMC - CYP - 1 FMC - CYP - III-B



CYPERMETHRIN STEP III WASTE

Components %

NaCN 1-3 NaCl 10-15 Na₂CO₃ 5-10 FMC 51055 3-8 Cypermethrin 500-800 ppm

Sample Method/Frequency

Grab-1/campaign

Test Method

STD Method 412B FMC - FRM - 40 ASTM - (D513) 31 FMC - CYP - IIIB FMC - CYP - XI



CYPERMETIIRIN WASTE - OIL DRY/SAMPLE JARS, MISC.

Components, :

٠,٠

Cypermethrin 100-800 ppm NaCN 1-2 FMC 39338 1-3 MeOH 1-3 NaOH 0-1 Oil Dry - Balance

Sample Method/Frequency

Grab-1/campaign

Test Method

FMC - - CYP - XI STD Method 412-B FMC - CYP - IVB GC A% FMC 285 Filtration



CYPERMETHRIN SPENT CARBON

Component %

Activated Carbon 98-99
Heptane
Methanol

- Balance

Sample Method/Frequency

Grab-1/campaign

Test Method

Filtration GC A%



CYPERMETHRIN WASTE HEPTANE

Component %

Heptane 60-80 DV Acid Chloride 5-10 Water Balance

Sample Method/Frequency

Grab-1/Campaign

Test Method

FMC - CYP - 1 FMC - CYP - 1 Karl Fisher

TABLE 1



Facilities containing Hazardous Wastes

Item Number	Material	Volume (Gal.)	Location
T-203	90% Carbon Tet	3000	Bldg. 34 Area
T-353	Chloroacetylenics	1000	•
T-411 (2), 412 (2), 413	Methanol	10,000 ea.	
T-440	Brine	100,000	
T-551	3% Carbon Tet	10,000	
T-556	3% Sodium Cyanide	5,000	
T-17	Isopropanel	5,000	Bldg. 91 Area
T-18	Organics	3,000	
T-23	Treated Waste Water	5,000	۵
T-23	19 19 19	5,000	
T-22	10 10	10,000	
Fire Water Pend	Pounce Contamination	38,000	
Waste Water Storage	10 10	30,000	
T-21	Untreated Waste Water	10,000	
m 0373	Λ: 1 B	10.000	Building 6 Area
T-9273	0i1 B	10,000	buttating o Ates
T-3466	011 B	13,000	
T-3469, 3470 3471	Sodium Bromide	13,000 ea.	
T-17363, 17364	Sodium Sulfide	12,000 ea.	
T-17373	Sodium Sulfide	10,000	
T-20447	Sodium Sulfide	100,000	



Inc

Page 2
Facilities containing Hazardous Wastes

Item Number	Material	Volume	Location
V-2230, 2231, 2232	Coal Filters	8,000 ea.	W. of J. Zink
Calgon Vesseis (4)	Activated Carbon	9,000 ca.	Calgon Bldg 7-OH Shop
			• • • • • • •
T-600; 17183; 17184; 590; 593	Allyl Ether	10,000 ea.	Bldg. 9 Area
	• • • • • • • • • • • • •		
T-2209	7-Oil Oil (Decanter)	1,160	7-Oll Area
T-2203A, 2203B	Wuste Organics	29,000 ea.	•
T-2204A, 2204B	Waste Organics	4,300 ea.	i.
V-1211, 1212, 1518, 1519, 3211, 3212, 3518, 3519	7-Oll Tar (Tar Neceivers)	190 ea.	
V-211, 212		60 ca.	
T-1221, 1221A, 1221B 1221C, 1221D, 1221E, 1221F	Tar Buggies	150 ca.	
T-1281-3	Settling Tank	5,160	
T-2201	Waste Tar	2,500	
T-1210, 3210	Emergency Quench Pit	11,500	
Effluent Busins (3)	7-Oil Tar, Ether, Xylene Sludge	101,600 Tetal	
Retention Basia (North and South)	7-OH Oils, Grease, Sludge	1,000,000 Tetal	i.
T-2501, 2502, 4301	Waste Water	1,500,000 each	
T-506	N. Copper Settler	50,000	
T-1827	S. Copper Settler	60,000	
T-3570A, B. C	Copper Muste Mater	102,430 each	






Item Number	<u>Material</u>	Volume	Location
T-3571	Copper Waste Water	540,000	
T-3567	Copper Sludge	10,150	· ·
T-1723	Aqueous Waste	210	








R = Potential Spill Area

- 1. Name DV Ester
- 2. Pollution Potential High
- 3. Spill Receiving System Containment Area, Sump
- 4. Counter Measures Recovery and/or Contract
 - . Disposal
- 5. Removal Available
- 6. Reporting Environmental Incident Report
- 7. Start-up/Shut-down Wastes No S-U/S-D Wastes

- 8. Frequency of upsets/failures Unknown
- 9. Location Continuous Intermittent Infrequent
 - a. Pump Shafts
 - b. Agitators
 - c. Valve Stems
 - d. Vent Systems
 - e. Sampling Prints
 - f. Level Controllers
 - g.
 - h.
- 10. Inspection/Maintenance-Adequate
- 11. Previous Incidents -
- 12.

BLOCK DIAGRAM




& - Potential Spill Area

- Monomers Name -
- 2. Pollution Potential -High
- 3. Spill Receiving System WTS
- 4. Counter Measures NP
- 5. Removal A (If contained)
- 6. Reporting Environmental Incident
- 7. Start-up/Shut-down Wastes No S-U/S-D Wastes

- Frequency of upsets/failures -Unknown
- Continuous Location: Intermittent Infrequent
- a. Pump Shafts
- b. Agitators
- c. Valve Stems
- d. Vent Systems e. Sampling Pts.
- Yacuum jet dschg,
- Inspection/Maintenance -10. Adequate
- 11. Previous incidents -
- 12.

X




= Potential Spill Area

- 1. Name Pounce (FMC 33297)
- 2. Pollution Potential High
- 3. Spill Receiving System Containment Area
- 4. Counter Measures Recovery and/or Special Disposal
- 5. Removal A
- 6. Reporting Environmental Incident
- 7. Start-up/Shut-down Wastes No S-U/S-D Wastes

- 8. Frequency of upsets/failures Unknown
- 9 Location: Continuous Intermittent Infrequent
 - a. Pump Shafts
 - b. Agitators
 - c. Valve Stems
 - d. Vent Systems
 - e. Sampling Pts.
 - •
 - h
- 10. Inspection/Maintenance Adequate
- 11. Previous incidents -
- 12. Comments -






- 1. Name Ethion, Sodium Bromide Recovery Sodium Sulfide Recovery
- 2. Pollution Potential Ethion High NaBr - Med. Na.S - High
- 3. Spill Receiving System WTS
- 4. Counter Measures NP
- 5. Removal A (If Contained)
- 6. Reporting Environmental Incident
- 7. Start-up/Shut-down Wastes No S-U/S-D Wastes .

- Frequency of upsets/failures Unknown
- Intermittent Location: Continuous Infrequent a. Pump Shafts
- b. Agitators c. Valve Stems
- . d. Vent Systems
- e. Sampling Pts.
- f. Piping
- h.
- Inspection/Maintenance -10. Adequate
- Previous incidents -11. Oct. 1971, Toluene B covery System, Unknown, 1, Effect Unknown Quantity 12.
 - (500 gals)

ELOCK DIAGRAM



- 1. Name 7-Hydroxy
- 2. Pollution Potential High
- -3. Spill Receiving System WTS
- 4. Counter Measures NE
- 5. Removal A (If Contained)
- 6. Reporting Environmental Incident
- 7. Start-up/Shut-down Wastes No S-U/S-D Wastes

- 8. Frequency of upsets/failures Unknown
- 9. Location: <u>Continuous</u> <u>Intermitrent</u> <u>Infrequent</u>

 a. Pump Shafts x
- b. Agitators
- c. Valve Stens
- d. Vent Systems
- e. Sampling Pts.
- f. Level Controllers
- 8
- h.
- 10. Inspection/Maintenance Adequate
- 11. Previous incidents -
- 12.



Section 4.0 - Wastewater Treatment System

It is plant policy to operate all production units at conditions that result in the minimum discharge of pollutants in the wastewater streams. All wastewater streams from the various production units (south of Patapsco Avenue) flow to the plants' wastewater treatment facility prior to discharge into Curtis Bay. A description of this facility including appropriate maintenance and operational items are given in the following sections.

The Pounce manufacturing facility (north of Patapsco Avenue) is surrounded by curbing that directs any wastewater to a sump. The sump contents are pumped into holding tanks. No wastewater is discharged to an outfall that does not meet the NPDES permit requirements for this operation.



Section 4.1 - Description

The waste water treatment facility is divided into two parts, the plant general and the 7-OH treatment systems. The plant general system treats the following streams:

PLANT GENERAL SYSTEM

- 1. Wastewater from all production units other than 7-OH.
- 2. Clean wastewaters from the 7-OH unit.
- 3. Storm water from the central plant area not including the southeast section or northern plant areas.
- 4. Wastewater from the 7-OH units after its specific treatment.


These streams are collected in manhole 105, neutralized in pH adjustment tank T-2505, equalized in equalization tank T-2501, contacted with acid gases from incinerator B-2201, neutralized again in the pH adjustment basin and then pumped to an underwater discharge point in Curtis Bay from the final surge basin.

The 7-OH treatment system treats the following streams:


- 1. Wastewater from the 7-0H unit.
- 2. Storm water from the 7-OH area.

Storm waters are collected in two retention ponds. Wastewaters are collected in the basin waste lift sumps T-2211 and T-2204. Both streams are then pumped into settling basins for removal of heavy oils, treated for reduction of entrained oils and then discharged to the plant general manhole 105. Heavy oils removed by settling are burned in incinerator B-2201.

Two full time operators are required for these treatment systems. A schemetic of the combined wastewater systems is included in this section.



Agricultural Chemical Group 1701 East Patapsco Avenue Box 1616 Baltimore Maryland 21203 (301) 355 6400



EMC

FMC - Baltimore, Maryland

PLANT CLOSURE PLAN

PURPOSE: The following procedure has been prepared to comply with Resource Conservation and Recovery Act (RCRA) regulations listed 5/19/80, to become effective 5/19/81. This plan must be updated annually (and amended as required) according to procedures described in the RCRA Regulations and must be kept at the plant site at all times.

A. Standards

The facility must be closed in a manner that minimizes the need for further maintenance and controls, minimizes or eliminates to the extent necessary to protect human health and the environment, post-closure escape of hazardous waste, hazardous waste constituents, leachate, contaminated rainfall, or waste decomposition products to the ground water, or surface waters or to the atmosphere.

B. Schedule

Upon finalization of the decision to cease operation of the plant as a production or storage facility, the following must be done.

1. Submit this closure plan to the EPA Regional Administrator located at the following address:

US EPA, Region 3
Solid Waste Program
6th & Walnut Streets
Philadelphia, Pennsylvania 19106
Phone: 215-597-9814

This must be done at least 180 days before the expected date at which closure is to begin.

- 2. The above mentioned Regional Administrator will notify, approve or disapprove this plan within 90 days of receipt, and after providing FMC and the affected public (through a newspaper notice) the opportunity to submit written comments.
- 3. Within 90 days after receiving the final volume of hazardous waste, FMC must treat all hazardous wastes in storage or in treatment or remove them from the site or dispose of onsite in accordance with the closure plan.

Agricultural Chemical Group 1701 East Patapsco Avenue Box 1616 Baltimore Maryland 21203 (301) 355 6400



ACCOUNTY THE WAY

FMC - Baltimore, Maryland

PLANT CLOSURE PLAN

1	Notify personnel of impending closure date
2.	Cancel incoming material orders and shipments. Date complete
3.	Terminate production Schedule completion
	Ethion line date complete
	Schedule completion
	Monomers line date complete
	Schedule completion
	DV Ester line date complete
	Schedule completion
	7-Hydroxy line date complete
	Schedule completion
	Pounce line date complete
	Schedule completion
	WILLIAM TIME descr combined
	Schedule completion
4.	Ship out products from warehouses.
	Scheduled completion date
	Date completed
5.	Ship out, or return excess raw
	materials, empty containers, pallets, bags, drums, et
	Scheduled completion date
	Date completed

C. Procedure

- 1. Remove all hazardous waste residues from any tanks, discharge control equipment (such as dust collectors), or discharge containment structures. Place in approved containers for treatment or disposal.
- 2. Testing procedures and results must document the condition of the liquid (wash & waste water) surface impoundment to verify its status.
 - (a) If non-hazardous no further action is necessary.

Agricultural Chemical Group 1701 East Patapsco Avenue Box 1616 Baltimore Maryland 21203 (301) 355 6400

FMC - Baltimore, Md.



Plant Closure Plan

- (b) If test results prove the liquid a hazardous waste, all standing liquid must be pumped up and placed in drums or tank vehicles for treatment or disposal. Also, waste, waste residues, and all underlying or contaminated surrounding soil will be excavated and placed into approved disposal contianers also for treatment or disposal. as dictated by the proper authority.
- 3. Remove all incinerator residues (including but not limited to ash, scrubber waters and scrubber sludges) from the incinerator. Place in approved containers and test. If test results so indicate, treat the waste so as to render it no longer hazardous, or store until disposed of in an approved manner.

D. Waste Inventory

The maximum inventory of stored waste is anticipated not to exceed 600 drums, (30,000 gal. or comparable volume), placed 4 drums per pallet. The areas used for palletized waste storage may range from approximately 1000 - 5000 sq. ft. of storage area, depending upon stacking height. One storage area is located north of 7-Hydroxy Plant I and another is located east of B-34.

E. Decontamination (Part I)

1. The estimated volumes of hazardous wastes that would have to be disposed of, their disposal costs, primary and alternate disposal sites are given below.

Waste Description	Estimated on hand inventory	Unit Cost C (\$)	Total Disposal Cost (K \$)	Disposal Site
T-2501/2502/4301 Solid Residue	1,000,000 P	0.10	100	C.W.M N.Y.
Lab Glassware	10 D	650.00	6.5	Rollins - N. J.
DVE Brine	20,000 G	0.16	3.2	Chem-Clear, MD
DVE Step I/II/III Residues	10,000 P	0.33	3.3	Rollins - N. J.
DVE Carbon Tet	15,000 P	0.14	2.1	Rollins - N. J.
DVE/Cyp./Calgon Carbon	10 D	650.00	6.5	Rollins - N. J.
DVE Misc. Solid	10 D	88.00	.880	C.W.M ALA
Cyp. Wate (Aq.)	40,000 P	0.04	1.6	DuPont - N. J.
Cyp. Filter Cake	10 D	88.00	.88	C.W.M ALA
Cyp Misc. (solid)	10 D	88.00	.88	C.W.M ALA
Empty Cyanide Drums	100 D	48.00	4.8	C.W.M ALA
Sodium Cyanide Waste (Aq.)	500 G	3.00	1.5	C.W.M ALA
Empty Drums (Misc.)	300 D	48.00	14.4	C.W.M ALA
Pounce Waste (Solid)	10 D	650.00	6.5	, Rollins - N.J.
DV Acid Chloride	4000 G	.19	.760	DuPonr - N. J.

NOV 20

46.

Waste Description	Estimated on hand inventory	Unit Cost C (\$)	Total Disposal Cost (K \$)	Disposal Site
Ammonium Chloride Filter Cake	80 D	77.00	6.2	GSX - S.C.
TMOA Organic Waste	20,000 P	.16	3.2	Rollins - N.J.
Copper Sludge	100,000 G	1.00	100 K	SCA - N.J.
7-Hydroxy Tar/Misc.	50 D	77.00	3.9 K	GSX - S.C.
ONP Spillage	2 D	77.00	.16 K	GSX - S.C.
7-Nitro Bottoms	50 D	77.00	3.9 K	GSX - S.C.
MAC Column Packing	80,000 P	.10	8.0 K	GSX - S.C.
Basin Sludge	200 D	230.00	46 K	C.W.M ALA
Sodium Bromide Waste (Aq.)	15,000 G	.55	8.3 K	SCA - N. J.
Sulfide Tank Washings	2,000 G	3.00	6.0 K	SCA - N. J.
011 "B"	50,000 P	.19	9.5 K	Rollins - N. J.
P ₂ S ₅ Sweepings	12 D	NO OUTLE	T AT THIS TIME	•
Sodium Sulfide/Bromide Slud	ge 200 D	230.00	46 K	C.W.M ALA
Ethion Filter Cake	30 D	650.00	2.3	GSX - S. C.
Phthalic Anhydride Spillage	10 D	650.00	6.5	Rollins - N.J.
Cooling Tower Sludge	5 D	650.00	3.3	Rollins - N.J?
Diallyl Phthalate Waste	5 D	650.00	3.3	Rollins - N. 실. 출
Pounce Resin	5 D	650.00	3.3	Rollins - N. J. &

\$413,660

Agricultural Chemical Group 1701 East Patapsco Avenue Box 1616 Baltimore Maryland 21203 (301) 355 6400





PLANT CLOSURE PLAN

 Prior to cleanup and subsequent decontamination all known wastes and areas suspect of contamination will be tested to determine toxicity. Areas and wastes requiring further attention will be treated in the following manner.

a. Waste Materials

Waste materials will be subject to treatment so as to render them no longer considered as hazardous wastes or so as to render them suitable for placement in an approved dump location.

b. Process Equipment, Incinerator, Emission Control Equipment

Process equipment will be decontaminated in the following manner:

- 1. All equipment will be drained or emptied of all process residue. Such materials will be handled in an appropriate manner and placed in suitable containers.
- 2. All equipment will be vacuumed or washed or appropriately disposed of. The wash solution will be a caustic solution or another suitable decontamination solution.

c. Buildings

All buildings which have been used for chemical storage or production will be checked for contamination. Those found to be contaminated will be decontaminated using current appropriate methods or razed and suitably disposed of.

NOTE: All areas subject to decontamination activities will be subject to laboratory testing to assure that decontamination activities have been successful. Decontamination procedures will be repeated as required until acceptable results have been obtained.

d. Miscellaneous Containers

Dispose of combustible containers (usually bags) suspected to be contaminated by incineration.

Cans or drums, suspected of contamination should be triple-rinsed using solvent (usually water) used in making up the tank mix. This operation should be performed if possible during phase-out of the production process prior to shutdown. Triple rinsing must consist of rinsing the container three times with enough solvent to equal 10 percent of the volume of the container. The container should be disposed of in a proper manner as dictated





FMC - Baltimore, Maryland

PLANT CLOSURE PLAN

by the proper authorities.

It is further suggested that small cans or jugs (plastic or steel) be crushed or shredded if possible so as to minimize the bulk volume at the disposal site.

Cost Estimate for Facility Closure

Cost estimates have been provided by the following companies who may be used to annually update these costs.

<u>D1</u>	sposal Site Costs	<u>Abbreviation</u>
1.	E. I. DuPont de Nemours, Inc. Chambers Works Deepwater, New Jersey 08023 Phone (609) 299-5000	DuPont, N. J.
2.	Chem-Clear 1910 Russell Street Baltimore, Maryland 21230 Phone (301) 685-3910	CC
3.	Chemical Waste Management, Inc. P. O. Box 55 Emelle, Alabama 35459 Phone (205) 652-9531	CWM
4.	GSX Services Route #1, Box 255 Pinewood, SC 29125 Phone (803) 452-5003	GSX
5.	Rollins Environmental Services, Inc. P. O. Box 221 Bridgeport, New Jersey 08014 Phone (609) 467-3100	CWM
6.	SCA Chemical Service Co. Earthline Division 100 Lister Avenue Newark, New Jersey 07105 Phone (201) 465-9100	SCA



FMC - Baltimore, Maryland

PLANT CLOSURE PLAN

E. <u>Decontamination (Part II)</u>

Total Closure Cost

\$787,360


Note:

- A. If test borings and/or water monitoring indicate other areas of contamination, cost of removal, disposal, shipping, etc. must be added to costs supplied above.
- B. The Baltimore, Maryland plant site is operated under the effluent guidelines of the plants' NPDES permit. The plant would continue to abide by the NPDES permit requirements and effluent limitations during the entire post closure operation.

CERTIFICATE OF CLOSURE

When closure is completed, FMC must submit to the Regional Administrator (see address, page 1) certification both by the owner (FMC) and by an independent registered professional engineer that the facility has been closed in accordance with the specifications in the approved closure plan.

PLATE 1




PUBLIC WATER DISTRIBUTION

THE BALTIMORE MUNICIPAL WATER AUTHORITY UTILIZES 10 SURFACE WATER INTAKES LOCATED OUTSIDE THE STUDY AREA. THEY SERVE APPROXIMATELY 1,100,000 PEOPLE.

WELLS LOCATED OUTSIDE THE STUDY AREA. THEY SERVE APPROXIMATELY 120,830 PEOPLE.

THERE ARE NO KNOWN PRIVATE HOME WELLS IN THE STUDY AREA.





FOUR MILE RADIUS MAP

FMC CORPORATION, CURTIS BAY, MD